LOCATION	SIZE		CLASS B PATCH 10"			CLASS D PATCH 12"		CLASS B PATCH 13"				SAW CUTS		DOWEL BARS		TIE BARS 3/4"		PAVEMENT FABRIC		STRIP REFLEC CRACK CONTROL TREATMENT
				TYPE IV		TYPE II	TYPE III	TYPE II		TYPE IV										
			SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	FOOT	EACH	EACH	EACH	EACH	SQ YD	SQ YD	
	NB	SB	INTERSECTION	NB	SB	CROSSOVER	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	FOOT
MM 0.00	6x12	6x12						8	8			48	48	20	20	50				
MM 0.05	6x12							8				48		20						
MM 0.06	6x12	6x12						8	8			48	48	20	20					
MM 0.07	6x12	6x12						8	8			48	48	20	20					
MM 0.10	100x12									133.3		236		20				133.3		
MM 0.16		6x12							8				48		20					
MM 0.43		6x12							8				48		20					
MM 0.45	6x12	6x12						8	8			48	48	20	20					
MM 0.90	6x12	6x12						8	8			48	48	20	20					
MM 1.18	6x12	6x12						8	8			48	48	20	20					
MM 1.32	120x12	40x12								160	53.3	116	276	20	20	60	20	160	53.3	
MM 1.33		60x12									80		156		20		30		80	
MM 1.36	80x12	30x12								106.7	40	196	96	20	20	40	15	106.7	40	
MM 1.40	60x14	20x14		93.3	31.1							162	82	24	24	30		93.3	31.1	
MM 1.80	200x16	150x12		355.6	200							448	336	28	20	100	75	355.6	200	
MM 1.85		100x12			133.3								236		20		50		133.3	
MM 1.90		40x12			53.3								116		20		20		53.3	
MM 2.55	6x12	6x12						8	8			48	48	20	20					
MM 2.60	10x12	10x12						13.3	13.3			56	56	20	20					
MM 3.00		6x12							8				48		20					
MM 3.85		6x24					16						84		40				16	
MM 4.70	6x12					8														
MM 6.10	12x12		16										60		20				16	48
SUB-TOTALS			16	448.9	417.7	8	16	77.3	93.3	400	173.3	1598	1978	292	424	280	210	848.9	623	48
15% ANTICIPATED FAILURES			10	130		5	15	25.6		86										
TOTALS			26	996.6		13	31	196.2		659.3		3576		716		490		1471.9		48