

## GENERAL NOTES

- ① WHERE ANY PARTIAL DEPTH PATCH ENCOUNTERS A DETECTOR LOOP, THAT PORTION OF THE PATCH SHALL BE OMITTED
- ② THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- ③ ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

UTILITY	ABOVE GROUND	BELOW GROUND
* AMEREN IP		X
* AT&T ILLINOIS		X
* CHARTER COMMUNICATIONS, INC.		X
* CITY OF COLLINSVILLE		X
* VILLAGE OF MARYVILLE		X
* SOUTHWESTERN ELECTRIC COOPERATIVE, INC.	X	
* CITY OF TROY		X

MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY \*. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- ④ THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

DESCRIPTION	MARYVILLE WEIGH STATION LOOP AROUND
-------------	-------------------------------------

MIXTURE USE	POLY SURFACE	PARTIAL DEPTH PATCH
AC/PG	SBS PG 76-22	PG 64-22
RAP % (MAX)	10%	10%
DESIGN AIR VOIDS	4.0% @ Ndes=90	4.0% @ Ndes=90
MIX COMPOSITION (GRADATION MIXTURE)		IL 12.5
FRICTION AGG	MIXTURE "D"	MIXTURE "D"

MIXTURE USE	SHOULDERS	TOP LIFT SHOULDERS
AC/PG	PG 64-22	PG 64-22
RAP % (MAX)	30%	30%
DESIGN AIR VOIDS	2.0% @ Ndes=30	2.0% @ Ndes=30
MIX COMPOSITION (GRADATION MIXTURE)		
FRICTION AGG	BAM	BAM

**\*\* Top Lift Shoulders - Design this mix at 2.0% voids and add asphalt to reduce voids to 1.5%.  
Plan quantities for Bituminous Concrete Surface Course items are calculated using a unit weight of 112 lb/sq yd/in (59.8 kg/sq m/25 mm thickness).  
See special provision RECLAIMED ASPHALT PAVEMENT (RAP) (BOE) for RAP %.**

- ⑤ THE THICKNESS OF THE BITUMINOUS MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.
- ⑥ ALL AREAS DISTURBED FOR ANY REASON SHALL BE PERMANENTLY SEEDED AS DIRECTED BY THE ENGINEER. ALL AREAS DISTURBED BY THE CONTRACTOR OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE SEEDED AT THE CONTRACTOR'S EXPENSE.
- ⑦ SIGN BASE ON PARAPET WALL TO BE REUSED. ALL WORK REQUIRED FOR REMOVAL AND RELOCATION TO BE INCLUDED IN PAY ITEMS PROVIDED. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
- ⑧ UPON CLOSURE OF THE WEIGH STATION, THE ENGINEER SHALL CONTACT MASTER SEARGENT PAT JACKSON OF THE ILLINOIS STATE POLICE AT 618-346-3615 AND INFORM HER OF THE CLOSURE DATES.

## STANDARDS

000001-05  
001006  
442101-07  
701451-01  
701901-01  
720001-01  
720006-02  
720011-01  
728001-01  
729001-01

## COMMITMENTS

NONE

FILE NAME =	USER NAME = watersle	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES, STANDARDS, &amp; COMMITMENTS</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\WIDOT\WATERSLE\d0165625\d876d55-shr-plan.dgn		DRAWN -	REVISED -			55/70	60-81-2	MADISON	16	2
PLOT SCALE = 1/8" = 1' / IN.		CHECKED -	REVISED -						CONTRACT NO. 76D55	
PLOT DATE = 3/19/2018		DATE -	REVISED -						FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT	
						SCALE: _____	SHEET NO. 1 OF 1 SHEETS	STA. _____	TO STA. _____	