

LEGEND

- C - CAMERA
- ⓪ - POLE MOUNT CAMERA BOX
- Ⓛ - SIGNAL CONDUIT
- Ⓛ - POWER CONDUIT
- ⓐ - PROPOSED CAMERA
- ==== - PROPOSED UNDERGROUND CONDUIT
- - PROPOSED LIGHT POLE, 35'
- - PROPOSED MONITOR, WALL MOUNT
- ⊠ - EXISTING CONTROLLER
- ⊠ - EXISTING HANDHOLE
- ⊠ - EXISTING HEAVY DUTY HANDHOLE
- - EXISTING UNDERGROUND CONDUIT
- - EXISTING BURIED CABLE

ELECTRICAL GENERAL NOTES

- 1 THE LIGHTED SIGN "CLOSED" SHALL BE TURNED ON DURING THE WEIGH STATION SHUT DOWN AS DIRECTED BY THE ENGINEER.
- 2 ALL EXISTING AND PROPOSED RIGHT-OF-WAY LINES SHOWN ON THE PLAN SHEETS ARE GRAPHICAL REPRESENTATIONS AND SHALL NOT BE USED AS A MEANS OF ESTABLISHED OWNERSHIP IN ALL MATTERS RELATING TO RIGHT-OF-WAY. THE PLAT OF HIGHWAYS SHALL BE THE CONTROLLING DOCUMENT.
- 3 ALL AREAS DISTURBED FOR ANY REASON SHALL BE PERMANENTLY SEEDED AS DIRECTED. THE COST SHALL BE INCLUDED IN PAY ITEM FOR TRENCH AND BACKFILL FOR ELECTRIC WORK.

ALL AREAS DISTURBED BY THE CONTRACTOR OUTSIDE THE PROPOSED CONSTRUCTION SHALL BE SEEDED AT THE CONTRACTOR'S EXPENSE.
- 4 THE LOCATION OF THE LIGHT POLE SHALL BE APPROVED BY THE ENGINEER BEFORE CONSTRUCTING FOUNDATION.
- 5 LOCATIONS SHOWN FOR THE BURIED UTILITIES AND CONDUITS ARE APPROXIMATE.
- 6 ILLINOIS STATE LAW REQUIRES A 48 HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - * AMEREN IP (GAS & ELECTRIC)
 - * AT&T ILLINOIS (COMMUNICATIONS)
 - * CHARTER COMMUNICATIONS, INC (CABLE TV)
 - * CITY OF O'FALLON (WATER & SANITARY SEWER)
 - * VILLAGE OF SHILOH (SANITARY SEWER)

(MEMBERS OF J.U.L.I.E. PHONE (800)-892-0123 ARE INDICATED BY *)
NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
- 7 COORDINATION WITH THE DEPARTMENT'S BUREAU OF OPERATIONS IS REQUIRED BEFORE ANY TRENCHING SHALL BE DONE TO LOCATE HIGHWAY LIGHTING/PUMP STATION/INTELLIGENT TRANSPORTATION SYSYTEM FACILITIES AND TO COORDINATE OTHER FIELD ACTIVITIES. THE CONTRACTOR WILL BE RESPONSIBLE FOR LOCATING AND PROTECTING ALL UNDERGROUND IDOT OWNED UTILITIES.
- 8 ALL WORK, AS DIRECTED BY THE ENGINEER, ASSOCIATED WITH HOOKING UP THE VIDEO CAMERA DETECTION SYSTEM WITHIN THE CONFINES OF THE SCALE HOUSE SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE EACH FOR VIDEO CAMERA DETECTION SYSTEM AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GENERAL NOTES AND LEGEND

FILE NAME =	USER NAME = petelbm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND LEGEND	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cd:\pw\work\pwidot\petelbm\0167050\0875	56-sht-TS.dgn	DRAWN -	REVISED -			64	82-71-5	ST. CLAIR	7	3	
	PLOT SCALE = 20.0000 ' / IN.	CHECKED -	REVISED -			CONTRACT NO. 76D56					
	PLOT DATE = 3/16/2010	DATE -	REVISED -			SCALE: 1"=20'	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT