

URBAN
100% STATE

SUMMARY OF QUANTITIES

URBAN
100% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	-----	-----
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20		
40600300	AGGREGATE (PRIME COAT)	TON	156	156		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2258	2258		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	603	603		
40600990	TEMPORARY RAMP	SQ YD	736	736		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5238	5238		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.2	1.2		
40800030	AGGREGATE (PRIME COAT)	TON	5	5		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	137	137		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	31093	31093		
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	40334	40334		
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	189	189		
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	23	23		
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	84	84		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	43449	43449		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	349	349		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1126	1126		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1107	1107		
* 63001605	METAL POSTS	EACH	3	3		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	7		
63200310	GUARDRAIL REMOVAL	FOOT	1369.5	1369.5		
63301990	REMOVAL AND RE-ERECTTRAFFIC BARRIER TERMINAL, TYPE1	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		-----	-----	-----
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15685	15685		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1430	1430		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	78015	78015		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1458	1458		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	451	451		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1307	1307		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1430	1430		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	78015	78015		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1458	1458		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	451	451		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	648	648		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	720	720		
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	702	702		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4998	4998		
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	2	2		

FILE NAME = c:\pw\work\pwidot\washingtona\d0175198

USER NAME = washingtona
 4976d84-sh1-plan.dgn
 PLOT SCALE = 100.0000 ' / IN.
 PLOT DATE = 3/17/2010

DESIGNED -	-----	REVISED -	-----
DRAWN -	-----	REVISED -	-----
CHECKED -	-----	REVISED -	-----
DATE -	-----	REVISED -	-----

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9266	33RS-5	ST. CLAIR	42	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 76D64	