

GUARDRAIL SCHEDULE

LOCATION	LANE	GUARDRAIL REMOVAL	SPBGR TYPE A 6 FOOT POSTS	BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT	REMOVAL AND REINSTALLATION OF EXISTING TERMINAL	METAL POSTS	GUARDRAIL MARKERS TYPE A	TERMINAL MARKER DIRECT APPLIED
		(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
STA. 150+92 TO STA. 153+99	LT	266.5	229.0	1	1	3	4	2
STA. 216+87 TO STA. 220+51	LT	351.0	276.0	2			5	2
STA. 235+55 TO STA. 240+08	RT	427.0	352.0	2			5	2
STA. 262+22 TO STA. 265+73	LT	325.0	250.0	2			4	2
TOTAL		1369.5	1107.0	7	1	3	18	8

FILE NAME =
c:\pr_work\pwsdot\washingtonaq\j0175198

USER NAME = washingtonaq
j076d64-shr-plandgn
PLOT SCALE = 100.0000' / IN.
PLOT DATE = 3/17/2010

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
9266 33RS-5 ST. CLAIR 42 17
CONTRACT NO. 76064
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT