

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000	100% ST. CLAIR CO. 1000	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000	100% ST. CLAIR CO. 1000
25000200	SEEDING, CLASS 2	ACRE	0.25	0.25		* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	762.5	762.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7.2	7.2		* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	22	22	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7.2	7.2		63200310	GUARDRAIL REMOVAL	FOOT	3500	3500	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7.2	7.2		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
25100115	MULCH, METHOD 2	ACRE	0.25	0.25		67100100	MOBILIZATION	L SUM	1	1	
28100207	STONE RIPRAP, CLASS A4	TON	12	12		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
28200200	FILTER FABRIC	SQ YD	23	23		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	51	51		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13.7	12.9	0.8	70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	64	62	2	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3022	2932	90	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5126	4402	724
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	736	589	147	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41130	39806	1324
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	74	74		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	92	22	70
40600990	TEMPORARY RAMP	SQ YD	273	248	25	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	570	489	81
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	3588	3453	135	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	41130	39806	1324
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	0.4		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	92	22	70
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	84	84		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	186	186	
44000400	GUTTER REMOVAL	FOOT	33	33		* 78200300	PRISMATIC CURB REFLECTOR	EACH	22		22
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	416	416		* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	30	30	
44213200	SAW CUTS	FOOT	2009	2009		78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	22	22	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1141	1125	16	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	186	186	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	103	59	44	X4421000	PARTIAL DEPTH PATCHING	TON	22	22	
50102400	CONCRETE REMOVAL	CU YD	19.1	19.1		X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	195	195	
50800105	REINFORCEMENT BARS	POUND	180	180		* X7800200	PAINT PAVEMENT MARKING CURB	FOOT	60		60
54002020	EXPANSION BOLTS 3/4 INCH	EACH	40	40		Z0017202	DOWEL BARS 1 1/2"	EACH	805	805	
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	3	3							
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	2	2							
54248510	CONCRETE COLLAR	CU YD	3.1	3.1							
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	0.5	0.5							
60500060	REMOVING INLETS	EACH	1	1							
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2.4	2.4							
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1362.5	1362.5							

** Specialty Items*

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -			840	233RS	ST. CLAIR	31	4	
		CHECKED -	REVISED -			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT			
		DATE -	REVISED -			CONTRACT NO. 76067					