

SIDEROADS ON DOUGLAS/MILLSTADT RD				
STATION	SIDEROAD	EXISTING MATERIAL	CONCRETE SURFACE REMOVAL-BUTT (SQ. YD.)	HMA SURFACE REMOVAL-BUTT JOINT (SQ. YD.)
113+62.0		CONCRETE	73.33	
116+76.0	ROENICKE RD.	HMA		91.67
116+76.0	ROENICKE RD.	HMA		91.67
198+60.0	SAXTOWN RD.	HMA		102.78
198+60.0	SAXTOWN RD.	HMA		102.78
239+25.6	MUELLER LN.	HMA		100.00
242+42.4	CLUBHOUSE LN.	HMA		69.44
267+74.0		HMA		30.56
			73.33	588.89
TOTAL			74	589

TEMPORARY RAMP SCHEDULE				
STATION	SIDEROAD	WIDTH (FT)	LENGTH (FT)	TEMPORARY RAMP (SQ. YD.)
113+62.0		22	5	12.22
116+76.0	ROENICKE RD.	66.0	5	36.67
116+76.0	ROENICKE RD.	66.0	5	36.67
198+60.0	SAXTOWN RD.	74.0	5	41.11
198+60.0	SAXTOWN RD.	74.0	5	41.11
239+25.6	MUELLER LN.	72.0	5	40.00
242+42.4	CLUBHOUSE LN.	50.0	5	27.78
267+74.0		22.0	5	12.22
				247.8
TOTAL				248

NORTH AND SOUTH - FLORAVILLE RD.				
STATION	SIDEROAD	EXISTING MATERIAL	CONCRETE SURFACE REMOVAL-BUTT (SQ. YD.)	HMA SURFACE REMOVAL-BUTT JOINT (SQ. YD.)
0+00	FLORAVILLE RD.	HMA		73.33
4+26	FLORAVILLE RD.	HMA		73.33
			0.00	146.67
TOTAL			0	147

TEMPORARY RAMP SCHEDULE				
STATION	SIDEROAD	WIDTH (FT)	LENGTH (FT)	TEMPORARY RAMP (SQ. YD.)
0+00	FLORAVILLE RD.	22.0	5	12.22
4+26	FLORAVILLE RD.	22.0	5	12.22
				24.4
TOTAL				25

MAILBOX TURNOUTS				
STATION	RT/LT	BITUMINOUS MATERIALS (PRIME COAT) (TON)	INC. HMA SURFACING (TON)	AGG. SURF. CSE., TYPE A (TON)
130+48.8	RT	0.005	2.33	0.83
132+60	RT			2.85
145+80	RT			4.15
148+44	RT	0.007	3.11	0.40
187+51.2	LT			3.70
189+36.2	LT			2.90
194+90.4	LT	0.003	1.6	0.20
203+88	LT			3.00
205+99.2	LT			6.00
214+44	LT			3.00
226+58.4	LT			3.00
		0.016	7.04	30.03
TOTAL		0.02	7	30

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---			840	233RS	ST. CLAIR	31	9
		CHECKED - ---	REVISED - ---			CONTRACT NO. 76067				
		DATE - ---	REVISED - ---	SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT			