

GUARDRAIL REMOVAL					
LOCATION NUMBER	STATION		STATION	LOCATION DESCRIPTION	GUARDRAIL REMOVAL (FT)
1	127+84.8	TO	130+24.8	RT	240
2	127+84.8	TO	134+86.8	LT	702
3	131+01.6	TO	131+30.6	RT	29
4	133+12.8	TO	135+38.8	RT	226
5	166+92	TO	171+92	LT	500
6	168+74	TO	171+77	RT	303
7	174+68	TO	175+71	LT	103
8	174+34	TO	175+38	RT	104
9	179+06.4	TO	181+82.4	RT	276
10	179+31.4	TO	182+09.4	LT	278
11	199+12.8	TO	200+90.8	LT	178
12	208+10.4	TO	211+18.4	RT	308
13	209+16.0	TO	211+69	LT	253

TOTALS	3500
--------	------

GUARDRAIL SCHEDULE									
LOCATION NUMBER	STATION	TO	STATION	RT/LT	SPBGR, TYPE A 6 FT POSTS (FT)	SPBGR, TYPE A 9 FT POSTS (FT)	TBT, TYPE 1 (SPEC) TANGENT (EACH)	GUARDRAIL MARKERS, TYPE A (EACH)	TERMINAL MARKER - DIRECT APPLIED (EACH)
1	128+91	TO	130+41	RT	150		2	2 @ 50' SPACING	2
2	128+64	TO	134+64	LT	600		2	8 @ 75' SPACING	2
3	131+81.3	TO	132+00	RT	18.75		2	1 @ 9' SPACING	2
4	133+20	TO	136+01.3	RT	281.25		2	4 @ 70' SPACING	2
5	135+34	TO	136+34	LT			2		2
6	164+76.4	TO	165+76.4	LT			2		2
7	167+39.1	TO	170+01.6	RT		262.5	2	4 @ 65' SPACING	2
8	166+33.9	TO	171+33.9	LT		500	2	7 @ 71' SPACING	2
9	170+71.6	TO	171+71.6	RT			2		2
10	209+65.9	TO	212+78.4	LT	312.5		2	4 @ 78' SPACING	2
11	213+48.4	TO	214+48.4	LT			2		2
TOTAL					1362.5	762.5	22	30	22

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	840	233RS	ST. CLAIR	31	10
		PLOT SCALE = #SCALE#	REVISED - ---					CONTRACT NO. 76D67				
		PLOT DATE = #DATE#	DATE - -----	REVISED - ---				FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				