

THERMOPLASTIC PAVEMENT MARKING - LINE 4"								THERMOPLASTIC PAVEMENT MARKING - LINE 24" WHITE STOP BAR	PAINT PAVEMENT MARKING CURB
BEGINNING STATION	ENDING STATION	EDGELINE WHITE	SKIP-DASH YELLOW	NPZ		SOLID YELLOW			
				LT	RT				
		(FT)	(FT)			(FT)	(FT)		
DOUGLAS/MILLSTADT RD.									
113+62	TO 116+38	552.0	69						
116+38	TO 117+14	OMISSION							
117+14	TO 148+44	6260.0	783						
148+44	TO 159+00	2112.0	264		X	1056			
159+00	TO 177+48	3696.0	0	X	X	3696			
177+48	TO 188+04	2112.0	264	X		1056			
188+04	TO 198+18	2028.0	254						
198+18	TO 199+02	OMISSION							
199+02	TO 238+84.6	7965.2	996						
238+84.6	TO 239+66.6	82.0	21	OMISSION FOR ONLY RT					
239+66.6	TO 262+48.8	4564.4	571				11		
IN FRONT OF MEDIANS		40.0							
263+54.4	TO 267+74	839.2	105	X		419.6	11		
FLORAVILLE RD.									
0+00	TO 1+87	374.0	0	X	X	374	35	30	
1+87	TO 2+49	OMISSION							
2+49	TO 4+26	354.0	45	X		177	35	30	
TOTALS		30978.8	3372			6778.6	92	60	
TOTALS		30979	3372			6779	92	60	

DOUGLAS/MILLSTADT RD. SHORT TERM PAVEMENT MARKING					
BEGINNING STATION	ENDING STATION	SKIP-DASH YELLOW	WHITE STOP BAR 12"	WORK ZONE PM REMOVAL	
		(FT)	(FT)	(SQ. FT.)	
113+62	TO 267+74	4203.3	198.0	489.0	
TOTALS		4203.3	198.0	489.0	
TOTALS		4402		489	

FLORAVILLE RD. SHORT TERM PAVEMENT MARKING					
BEGINNING STATION	ENDING STATION	SKIP-DASH YELLOW	WHITE STOP BAR 12"	WORK ZONE PM REMOVAL	
		(FT)	(FT)	(SQ. FT.)	
0+00	TO 1+87	51.0	315.0	40.7	
1+87	TO 2+49	OMISSION			
2+49	TO 4+26	42.8	315.0	39.8	
TOTALS		94.0	630.0	80.4	
TOTALS		724		81	

PAVEMENT MARKERS			
LOCATION	RAISED REFLEC PAVEMENT MARK - DOUBLE AMBER	RAISED REFLECT MARK - REMOVAL	PRISMATIC CURB REFLECTORS
	(EACH)	(EACH)	(EACH)
DOUGLAS/MILLSTADT RD.			
STA. 113+62 TO STA. 116+76	5	5	
STA. 116 +76 TO STA. 198+60	102	102	
STA. 198+60 TO STA. 262+48.8	74	74	
STA. 264+07.2 TO STA. 267+74	5	5	
FLORAVILLE RD.			
STA. 0+00 TO STA. 1+87			11
STA. 1+87 TO STA. 2+49	OMISSION		
STA. 2+49 TO STA. 4+26			11
TOTALS	186	186	22

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -			840	233RS	ST. CLAIR	31	13
		CHECKED -	REVISED -			CONTRACT NO. 76D67				
		PLOT SCALE = #SCALE#	DATE		SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. _ [ILLINOIS] FED. AID PROJECT		
		PLOT DATE = #DATE#								