

CLASS B PAVEMENT PATCHING 8 INCH SCHEDULE

MILE STATION	LANE	LENGTH (FT)	LANE WIDTH (FT)	CLASS B PATCH TYPE II (SQ YD)	CLASS B PATCH TYPE III (SQ YD)	CLASS B PATCH TYPE IV (SQ YD)	DOWEL BARS 1.5 in. (EACH)	TIE BARS (EACH)	PAVEMENT FABRIC (SQ YD)	SAWCUT (FT)
0.030	NB	25.0	11.0			30.6	20	12	30.6	72.0
0.100	NB	6.0	11.0	7.3			20			34.0
0.120	NB	6.0	11.0	7.3			20			34.0
0.120	SB	6.0	11.0	7.3			20			34.0
0.130	NB	6.0	11.0	7.3			20			34.0
0.130	SB	6.0	11.0	7.3			20			34.0
0.140	NB	6.0	11.0	7.3			20			34.0
0.140	SB	6.0	11.0	7.3			20			34.0
0.150	SB	25.0	11.0			30.6	20	12	30.6	72.0
0.160	NB	6.0	11.0	7.3			20			34.0
0.160	SB	6.0	11.0	7.3			20			34.0
0.165	NB	6.0	11.0	7.3			20			34.0
0.165	SB	6.0	11.0	7.3			20			34.0
0.180	NB	6.0	11.0	7.3			20			34.0
0.180	SB	6.0	11.0	7.3			20			34.0
0.200	NB	8.0	11.0	9.8			20			38.0
0.200	SB	8.0	11.0	9.8			20			38.0
0.210	NB	15.0	11.0		18.3		20		18.3	52.0
0.210	SB	15.0	11.0		18.3		20		18.3	52.0
0.220	SB	8.0	11.0	9.8			20			38.0
0.240	NB	6.0	11.0	7.3			20			34.0
0.250	NB	6.0	11.0	7.3			20			34.0
0.250	SB	6.0	11.0	7.3			20			34.0
0.260	NB	6.0	11.0	7.3			20			34.0
0.260	SB	6.0	11.0	7.3			20			34.0
0.300	NB	6.0	11.0	7.3			20			34.0
0.300	SB	6.0	11.0	7.3			20			34.0
0.310	NB	6.0	11.0	7.3			20			34.0
0.310	SB	6.0	11.0	7.3			20			34.0
0.330	NB	6.0	11.0	7.3			20			34.0
0.330	SB	6.0	11.0	7.3			20			34.0
0.350	NB	6.0	11.0	7.3			20			34.0
0.360	NB	6.0	11.0	7.3			20			34.0
0.360	SB	6.0	11.0	7.3			20			34.0
0.400	NB	6.0	11.0	7.3			20			34.0
0.400	SB	6.0	11.0	7.3			20			34.0
0.420	SB	15.0	11.0		18.3		20		18.3	52.0
0.450	NB	6.0	11.0	7.3			20			34.0
0.450	SB	6.0	11.0	7.3			20			34.0
0.460	SB	6.0	11.0	7.3			20			34.0
SUBTOTAL:				263	54.9	61.1	800	24	116.1	1502

CLASS B PAVEMENT PATCHING 8 INCH SCHEDULE

MILE STATION	LANE	LENGTH (FT)	LANE WIDTH (FT)	CLASS B PATCH TYPE II (SQ YD)	CLASS B PATCH TYPE III (SQ YD)	CLASS B PATCH TYPE IV (SQ YD)	DOWEL BARS 1.5 in. (EACH)	TIE BARS (EACH)	PAVEMENT FABRIC (SQ YD)	SAWCUT (FT)
0.470	NB	6.0	11.0	7.3			20			34.0
0.470	SB	6.0	11.0	7.3			20			34.0
0.500	SB	10.0	11.0	12.2			20			42.0
0.510	NB	6.0	11.0	7.3			20			34.0
0.510	SB	6.0	11.0	7.3			20			34.0
0.550	SB	8.0	11.0	9.8			20			38.0
0.590	NB	6.0	11.0	7.3			20			34.0
0.590	SB	6.0	11.0	7.3			20			34.0
0.600	SB	6.0	11.0	7.3			20			34.0
0.610	SB	6.0	11.0	7.3			20			34.0
0.640	NB	8.0	11.0	9.8			20			38.0
0.640	SB	8.0	11.0	9.8			20			38.0
0.700	SB	6.0	11.0	7.3			20			34.0
0.720	NB	8.0	11.0	9.8			20			38.0
0.750	NB	6.0	11.0	7.3			20			34.0
0.750	SB	6.0	11.0	7.3			20			34.0
0.790	NB	6.0	11.0	7.3			20			34.0
0.790	SB	6.0	11.0	7.3			20			34.0
0.840	NB	6.0	11.0	7.3			20			34.0
0.840	SB	6.0	11.0	7.3			20			34.0
0.920	NB	6.0	11.0	7.3			20			34.0
0.920	SB	6.0	11.0	7.3			20			34.0
0.950	NB	6.0	11.0	7.3			20			34.0
0.960	NB	6.0	11.0	7.3			20			34.0
1.000	NB	6.0	11.0	7.3			20			34.0
1.000	SB	6.0	11.0	7.3			20			34.0
1.010	NB	6.0	11.0	7.3			20			34.0
1.010	SB	6.0	11.0	7.3			20			34.0
1.020	NB	6.0	11.0	7.3			20			34.0
1.050	NB	6.0	11.0	7.3			20			34.0
1.060	NB	6.0	11.0	7.3			20			34.0
1.060	SB	6.0	11.0	7.3			20			34.0
1.090	NB	6.0	11.0	7.3			20			34.0
1.090	SB	6.0	11.0	7.3			20			34.0
1.100	SB	8.0	11.0	9.8			20			38.0
1.120	NB	6.0	11.0	7.3			20			34.0
1.120	SB	6.0	11.0	7.3			20			34.0
1.130	SB	6.0	11.0	7.3			20			34.0
1.150	NB	6.0	11.0	7.3			20			34.0
1.150	SB	6.0	11.0	7.3			20			34.0
SUBTOTAL:				309.4	0	0	800	0	0	1388

NOTE: TIE BARS SHALL BE 3/4" DIAMETER.

FILE NAME =	USER NAME = watersle	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\p\001\WATERSLE\00174282\d876d71-sh1-plan.dgn		DRAWN -	REVISED -			735	55RS-5	MADISON	10	6
PLOT SCALE = 1/8" = 1' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76D71				
PLOT DATE = 3/16/2010		DATE -	REVISED -			FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				
						SCALE: _____	SHEET NO. 2 OF 3 SHEETS	STA. _____	TO STA. _____	