

SUMMARY OF QUANTITIES

FAU 9189 | FAU 9228

FAU 9189 | FAU 9228

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 LOCATION #1	I000 LOCATION #2	I000 LOCATION #3
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16.1	8.7	2.2	5.2
40600300	AGGREGATE (PRIME COAT)	TON	78	42	11	25
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2272	1173	296	803
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1804			1804
40600990	TEMPORARY RAMP	SQ YD	497	211	36	250
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4380	2346	592	1442
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	34983	27930	7053	
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	356	37		319
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	65	43		22
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	184			184
44213100	PAVEMENT FABRIC	SQ YD	605	80		525
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	13			13
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	1	1
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1			1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1			1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6636	3184	1058	2394
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	621	403		218
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30373	16779	5951	7643
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1938	1622	80	236
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	463	311	80	72
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11322	8097	300	2925
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	621	403		218
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30373	16779	5951	7643
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1938	1622	80	236
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	463	311	80	72
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	361	238	33	90

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 LOCATION #1	I000 LOCATION #2	I000 LOCATION #3
*78200300	PRISMATIC CURB REFLECTOR	EACH	108			108
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	361	238	33	90
*80300100	LOCATING UNDERGROUND CABLE	FOOT	75			75
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	3105			3105
*Z0036200	PAINT CURB	FOOT	1254			1254
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0075310	TIE BARS 3/4"	EACH	874	112		762
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.33	0.33	0.34
*specialty Hems						

FILE NAME =	USER NAME = weterale	DESIGNED -	REVISED -
ca\pwwork\PIWID01\WATERSL\0174384\d8	6d75-shr-plan.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8" = 100,0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/17/2018	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.

F.A. RTE. 9228 / 9189	SECTION (Z-1)RS-2, 29RS-6	COUNTY ST. CLAIR	TOTAL SHEETS 33	SHEET NO. 3
CONTRACT NO. 76075				
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				