

PATCHING SCHEDULE								
PATCH #	STA	RT/LT	WIDTH	LENGTH	TY 2	SAW CUTS	DOWEL BARS	
1	684+50	RT	11	6	7.33	45	20	*
2	691+50	RT	11	6	7.33	45	20	*
3	693+50	RT	11	6	7.33	45	20	*
4	694+50	RT	11	6	7.33	45	20	*
5	697+50	RT	11	6	7.33	39	20	
6	702+50	RT	11	6	7.33	39	20	
7	725+00	RT	11	6	7.33	39	20	
8	729+00	RT	11	6	7.33	39	20	
9	733+00	RT	11	6	7.33	39	20	
10	734+00	RT	11	6	7.33	39	20	
11	735+00	RT	11	6	7.33	39	20	
12	739+18	RT	11	6	7.33	39	20	
13	744+50	RT	11	6	7.33	39	20	
14	746+00	RT	11	6	7.33	39	20	
15	749+00	RT	11	6	7.33	39	20	
16	751+00	RT	11	6	7.33	39	20	
17	755+00	RT	11	6	7.33	39	20	
18	757+00	RT	11	6	7.33	39	20	
19	760+00	RT	11	6	7.33	39	20	
20	766+00	LT	11	6	7.33	39	20	
21	765+00	LT	11	6	7.33	39	20	
22	763+00	LT	11	6	7.33	39	20	
23	757+00	LT	11	6	7.33	33	20	
24	756+00	LT	11	6	7.33	39	20	
25	755+00	LT	11	6	7.33	33	20	
26	753+00	LT	11	6	7.33	39	20	
27	752+75	LT	11	6	7.33	39	20	
28	752+00	LT	11	6	7.33	39	20	
29	750+00	LT	11	6	7.33	39	20	
30	749+00	LT	11	6	7.33	33	20	
31	746+00	LT	11	6	7.33	33	20	
32	737+00	LT	11	6	7.33	39	20	
33	734+00	LT	11	6	7.33	33	20	
34	733+00	LT	11	6	7.33	33	20	
35	731+00	LT	11	6	7.33	39	20	
36	730+00	LT	11	6	7.33	39	20	
37	729+00	LT	11	6	7.33	33	20	
38	724+50	LT	11	6	7.33	45	20	*
39	721+50	LT	11	6	7.33	45	20	*
40	720+50	LT	11	6	7.33	45	20	*
41	719+50	LT	11	6	7.33	45	20	*
42	708+00	LT	11	6	7.33	39	20	
43	707+50	LT	11	6	7.33	39	20	
44	705+50	LT	11	6	7.33	39	20	
45	702+50	LT	11	6	7.33	39	20	
TOTALS					329.9	1761	900	

\* INDICATES CUTTER SECTION

THERMOPLASTIC PAVEMENT MARKING-4"						
LOCATION		LINE 4 INCH				
		SOLID WHITE	SOLID YELLOW	SOLID YELLOW	YELLOW SKIP DASH	
STA	TO STA	(FOOT)	(FOOT)	(FOOT)	(FOOT)	
606+00	TO 606+08	16	8			
606+08	TO 624+93	3770			471.25	
638+26	TO 642+80	908		454	113.5	
642+80	TO 649+03	1246	623		155.75	
651+20	TO 654+14	588	294		73.5	
654+14	TO 658+00	772			96.5	
658+00	TO 668+58	2116		1058	264.5	
668+58	TO 678+11	1906	953	953		
678+11	TO 689+00	2129	1089		272.25	
689+00	TO 729+35	7952			1008.75	
729+35	TO 738+16	1762		881	220.25	
738+16	TO 740+36	440			55	
740+36	TO 748+93	1714	857		214.25	
748+93	TO 771+61	4536			567	
SUB TOTAL:		29855	3824	3346	3512.5	
TOTAL:					40537.5	

RAISED PAVEMENT MARKERS			
LOCATION		RAISED REFLECTOR PAVEMENT MARKERS TWO WAY AMBER	RAISED REFLECTOR PAVEMENT MARKERS REMOVAL
STA	TO STA	(EACH)	(EACH)
ROOTS RD			
606+00	TO 624+93	24	22
638+26	TO 649+03	13	13
651+20	TO 771+61	150	150
SUBTOTAL:		187	185

TEMPORARY RAMPS	
LOCATION/DESCRIPTION	TEMPORARY RAMPS (SQ YD)
Sta 606+00/ Begin Job	12.2
Sta 618+70 (LT)/ Oak view Rd.	33.3
Sta 624+93	12.2
Sta 638+26	12.2
Sta 649+03	12.2
Sta 651+20	12.3
Sta 654+50 (LT)/ Collins Rd.	35.0
Sta 654+50 (RT)/ N. Klondike Rd.	35.0
Sta 683+50 (LT)/ Collins Rd.	42.2
Sta 721+08 (RT)/ S. Harmony Rd.	36.1
Sta 771+61/ End Job	12.2
TOTAL:	255

SHOULDER SCHEDULE					
LOCATION			LT/RT	HOT-MIX ASPHALT SHOULDERS 6"	AGGREGATE WEDGE SHOULDERS, TYPE B
STA	TO STA	STA		(SQ YD)	(TON)
606+00	TO 624+93	RT		631	8.98
638+26	TO 649+03	RT		359	5.11
651+20	TO 654+18	RT		99.3	1.41
654+82	TO 656+00	RT		39.3	0.56
669+00	TO 678+04	RT		301.3	4.29
696+45	TO 720+75	RT		810	11.53
721+41	TO 770+99	RT		1652.7	23.53
771+17	TO 771+25	RT		2.7	0.04
606+00	TO 618+40	LT		413.3	5.88
619+00	TO 624+93	LT		197.7	2.81
651+20	TO 654+18	LT		99.3	1.41
654+82	TO 656+00	LT		39.3	0.56
669+00	TO 683+12	LT		471.3	6.7
683+88	TO 716+44	LT		1085	15.45
726+68	TO 771+47	LT		1493	21.26
TOTAL:				7694.2	109.5

HMA RESURFACING						
LOCATION STA:	HMA SURFACE REMOVAL BUTT JOINT (SQ YD)	CONCRETE SURFACE REMOVAL BUTT JOINT 1/2" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	LEVELING BINDER 1" (TON)	HMA SURFACE COURSE 1.5" (TON)
606+00 (Begin)	146.7					
721+08 (RT)	63.9		0.02	0.10		7.20
683+50 (LT)	75.7		0.02	0.11		8.50
654+50 (LT)	61.1		0.02	0.09		6.80
654+50 (RT)	60.4		0.02	0.09		6.80
618+70 (LT)	61.1		0.02	0.09		6.80
606+00 to 624+93			1.50	6.90	259.1	388.70
638+26 to 649+03			0.82	3.95	147.4	221.10
651+20 to 771+61			9.20	44.15	1648.3	2472.40
624+93		146.7				
638+26		146.7				
649+036		146.7				
651+20		146.7				
771+61 (End)		146.7				
Add for dips @ 624+93						20
TOTALS	468.9	733.5	11.6	55.48	2054.8	3138.30

FILE NAME =	USER NAME = alford	DESIGNED -	REVISED -
alpe...work\VP\1001\VALFORDB\017484\1007...	d79-shr-plandgn	DRAWN -	REVISED -
PLOT SCALE = 1/8"=1'-0"		CHECKED -	REVISED -
PLOT DATE = 3/16/2010		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE. 050	SECTION 12.13RS	COUNTY RANDOLPH	TOTAL SHEETS 8	SHEET NO. 7
CONTRACT NO. 76079				
ILLINOIS FED. AID PROJECT				