

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	1000	-----	-----	CODE NO	ITEM	UNIT	1000	-----	-----		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	29	29		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	325	325			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.6	6.6		* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	8	8			
40600300	AGGREGATE (PRIME COAT)	TON	32	32		* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1	1			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1156	1156		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28202	28202			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	775	775		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	55	55			
40600990	TEMPORARY RAMP	SO YD	173	173		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	129	129			
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1780	1780		* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	9	9		* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	733	733		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	119	119			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	2494	2494		X4403300	CONCRETE MEDIAN REMOVAL	SO FT	30	30			
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	725	725									
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SO YD	132	132									
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SO YD	59	59									
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SO YD	176	176									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	679	679									
60621600	CONCRETE MEDIAN, TYPE SM	SO FT	30	30									
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	900	900									
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4									
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4									
63200310	GUARDRAIL REMOVAL	FOOT	915	915									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3									
67100100	MOBILIZATION	L SUM	1	1									
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1									
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1									
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1844	1844									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28202	28202									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	55	55									

**Specialty Items*

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			9108	104RS-4	MADISON	15	3	
		CHECKED -	REVISED -			CONTRACT NO. 76D80					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					