

SIDE ROAD AND ENTRANCE SCHEDULE						
LOCATION	OFFSET	TYPE	EXISTING SURFACE	WIDTH	LENGTH	INCIDENTAL HMA SURFACING
MILE STATION	RT/LT			FOOT	FOOT	
1.01	RT	SIDE ROAD BISCHOFF RD	BITUMINOUS	60	12.5	5.8
1.34	LT	COMMERCIAL	BITUMINOUS	34	3	0.8
1.60	RT	PRIVATE	BITUMINOUS	30	3	0.7
1.79	RT	PRIVATE	BITUMINOUS	30	3	0.7
1.80	RT	PRIVATE	BITUMINOUS	34	3	0.8
TOTAL						8.8

PATCHING SCHEDULE						
LOCATION	LANE	LENGTH	WIDTH	PAVEMENT PATCHING 10"		
				TYPE II	TYPE III	TYPE IV
MILE STATION	SOUTH OR NORTH BOUND	FOOT	FOOT	SQ YD	SQ YD	SQ YD
0.05	SOUTH BOUND	6	18	12.00		
0.13	SOUTH BOUND	6	11	7.33		
0.15	SOUTH BOUND	6	11	7.33		
0.15	NORTH BOUND	6	11	7.33		
0.63	NORTH BOUND	6	11	7.33		
0.63	SOUTH BOUND	6	11	7.33		
0.76	NORTH BOUND	8	11	9.78		
1.36	SOUTH BOUND	6	11	7.33		
1.48	NORTH BOUND	6	11	7.33		
1.72	SOUTH BOUND	6	11	7.33		
1.75	NORTH BOUND	6	11	7.33		
1.75	SOUTH BOUND	6	11	7.33		
1.80	NORTH BOUND	20	11		24.44	
1.80	SOUTH BOUND	12	11	14.67		
1.81	NORTH BOUND	25	11			30.56
1.82	SOUTH BOUND	20	11		24.44	
1.85	SOUTH BOUND	50	11			61.11
1.85	NORTH BOUND	45	11			55.00
SUBTOTAL				109.78	48.89	146.67
ANTICIPATED FAILURE (20%)				21.96	9.78	29.33
TOTAL				131.73	58.67	176.00

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - ---	REVISED - ---			9108	104R5-4	MADISON	15	5	
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			CONTRACT NO. 76D80					
	PLOT DATE = #DATE#	DATE - -----	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					
				SCALE: ----- SHEET NO. -- OF --- SHEETS STA. ----- TO STA. -----							