

MAILBOX TURNOUTS		
LOCATION	OFFSET	AGGREGATE SURFACE COURSE, TYPE B
MILE STA.	LT/RT	TONS
1.60	RT	7.2
1.72	RT	7.2
1.76	RT	7.2
1.80	RT	7.2
TOTALS		28.8

BUTT JOINT SCHEDULE		
LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
MILE STATION	SQ YD	SQ YD
0.01	233	40
0.34	0	21
0.49	0	21
0.52	0	21
0.55	0	21
1.83	542	50
TOTAL	775	173

GUARDRAIL SCHEDULE							
LOCATION		SPBGR REMOVAL	SPBGR TYPE A	TRAFFIC BARRIER TERM		GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER DIRECT APPLIED
MILE STATION	LT/RT	FOOT	FOOT	TY 1 SPL	TY 6	EACH	EACH
0.14	RT			1		1	
0.14	LT			1		1	
0.21	RT				1		
0.21	LT				1		
0.34	RT				1		
0.34	LT				1		
0.38	RT			1		1	
0.39	LT			1		1	
0.14 TO 0.21	RT	385	300				5
0.14 TO 0.21	LT	385	300				5
0.34 TO 0.35	RT	60					
0.34 TO 0.36	LT	85					
0.34 TO 0.38	RT		112.5				4
0.34 TO 0.39	LT		187.5				4
TOTALS		915	900	4	4	4	18