

SUMMARY OF QUANTITIES

URBAN

100% STATE
1000

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE			
				LOCATION 1	LOCATION 2	LOCATION 3	LOCATION 4
20200100	EARTH EXCAVATION	CU YD	157.33			157.33	
28100107	STONE RIPRAP, CLASS A4	SO YD	25	25			
28200200	FILTER FABRIC	SO YD	25	25			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1465		912	553	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1592.2	807.8	640	144.4	
40600990	TEMPORARY RAMP	SO YD	341.7	211.1	106.8	23.8	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	17.9	17.9			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	11889.4			10856	1033.4
44003100	MEDIAN REMOVAL	SO FT	859	556	303		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	341	202		124	15
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SO YD	246			169	77
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	283	105	93	74	11
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	944			944	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1202	435	696	49	22
60620000	CONCRETE MEDIAN, TYPE SB - 6.24	SO FT	859	556	303		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL NO	6	2	2	2	
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	0.25	0.25	0.25	0.25
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25	0.25	0.25	0.25
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.25	0.25	0.25	0.25
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.25	0.25	0.25	0.25
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.34		0.33	0.33
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.25	0.25	0.25	0.25
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.25	0.25	0.25	0.25
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	43178	31809	7000	3669	700
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	234	234			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	54413	21811	16850	14552	1200
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	550	550			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	562	562			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	180	180			

FILE NAME *	USER NAME * fmgtr	DESIGNED -	REVISED -
...	...	DRAWN -	REVISED -
...	...	CHECKED -	REVISED -
...	...	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D-BRESURFACING 2010-4	ST. CLAIR	49	3
CONTRACT NO. 76086			
ILLINOIS FED. AID PROJECT			