

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000	50% STATE 50% CITY 4025	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	143.1	139.8	3.3	
40600300	AGGREGATE (PRIME COAT)	TON	69.1	67.5	1.6	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	373	333	40	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	477.8	477.8		
40600990	TEMPORARY RAMP	SO YD	335.6	279.9	55.7	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2580	2520	60	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3859.6	3770	89.6	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	83	73	10	
42001200	PAVEMENT FABRIC	SO YD	683	683		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	14457.7	13391	1066.7	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	2817	2817		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	72	72		
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	610	610		
44213200	SAW CUTS	FOOT	20066	20066		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4870	4870		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1		
60602500	CONCRETE GUTTER, TYPE A	FOOT	1000	1000		
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SO FT	35	35		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6311	6311		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	175	175		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	36975	36975		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	120	120		
70300260	TEMPORARY PAVEMENT MARKING LINE 12"	FOOT	1250	1250		

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000	50% STATE 50% CITY 4025	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2104	2104		
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	175	175		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	36975	36975		
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1250	1250		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120	120		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	510	510		
*78200300	PRISMATIC CURB REFLECTOR	EACH	42	42		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	510	510		
*88600100	DETECTOR LOOP, TYPE I	FOOT	2400	2400		
X0325807	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1/2"	SO YD	31708	31708		
X4421000	PARTIAL DEPTH PATCHING	TON	182	182		
X4422025	PARTIAL DEPTH REMOVAL 2"	SO YD	1623	1623		
*X7800200	PAINT PAVEMENT MARKING CURB	FOOT	200	200		
Z0017202	DOWEL BARS 1 1/2"	EACH	8132	8132		
Z0075310	TIE BARS 3/4"	EACH	209	209		
40600895	CONSTRUCT TEST STRIP	EACH	1	1		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SO YD	14,457	13,391	1066	
44000400	GUTTER REMOVAL	FOOT	1,000	1,000		
44000200	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	35	35		
44213100	PAVEMENT FABRIC	SO YD	683	683		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	73	73		
X0326103	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - 1"	SO YD	31,708	31,708		

*Specialty Items

Rev.

FILE NAME = d876d88-shr-plan.dgn	USER NAME = District	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE:	SHEET NO. OF SHEETS STA. TO STA.	F.A.U. RTE. 8983	SECTION 202R	COUNTY MADISON	TOTAL SHEETS 24	SHEET NO. 3
PLOT SCALE = 102.4686' / IN.		CHECKED -	REVISED -				FED. ROAD DIST. NO. (ILLINOIS) FED. AID PROJECT		CONTRACT NO. 76D88		
PLOT DATE = 3/19/2010		DATE -	REVISED -								