

90% FED.
10% STATE IL 3 IL 15

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1 ST CLAIR SFTY-ID	LOCATION 2 MADISON SFTY-ID	LOCATION 3 MADISON SFTY-ID
67100100	MOBILIZATION	L SUM	1	0.33	0.33	0.34
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1			1
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SO FT	539			539
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	209000	141106	59492	8402
78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	18430	11774	5109	1547
78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	581			581
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	262			262
X7030068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SO FT	539			539
X7030070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	209000	141106	59492	8402
X7030076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	18430	11774	5109	1547
X7030078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	581			581
X7030090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	262			262

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES			

FILE NAME *	USER NAME * eJforab	DESIGNED -	REVISED -
c:\p\work\p\dot\el\forab\08188899\0876488-sht\plan\dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

VAR. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D8 STRIPING 2010-1	MADISON/ST. CLAIR	8	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 76E08	