

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE-1000-1A	
		UNIT	TOTAL QUANTITIES FEDERAL 90% STATE 10%
20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	121
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	108
20200100	EARTH EXCAVATION	CU YD	6690
20800150	TRENCH BACKFILL	CU YD	26
25000115	SEEDING, CLASS 1B	ACRE	1.74
25000350	SEEDING, CLASS 7	ACRE	1.74
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	279
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	209
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	209
25000700	AGRICULTURAL GROUND LIMESTONE	TON	3.5
25100115	MULCH, METHOD 2	ACRE	3.5
25100630	EROSION CONTROL BLANKET	SQ YD	1212
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	522
28000305	TEMPORARY DITCH CHECKS	FOOT	102
28000500	INLET AND PIPE PROTECTION	EACH	4
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	4076
35501318	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	SQ YD	787
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	3025
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	39
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	57
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	24
40600990	TEMPORARY RAMP	SQ YD	51
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N105	TON	1045
40800010	BITUMINOUS MATERIAL PRIME COAT	GALLON	2043
40800030	AGGREGATE PRIME COAT	TON	34
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	149
44000100	PAVEMENT REMOVAL	SQ YD	575
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	9511
44000400	GUTTER REMOVAL	FOOT	1059
44004000	PAVED DITCH REMOVAL	FOOT	174
44004250	PAVED SHOULDER REMOVAL	SQ YD	767
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2647
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	2778
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE-1000-1A	
		UNIT	TOTAL QUANTITIES FEDERAL 90% STATE 10%
48203003	HOT-MIX ASPHALT SHOULDERS, 1 1/2"	SQ YD	719
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2013
50105220	PIPE CULVERT REMOVAL	FOOT	48
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	18
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	8
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	26
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	34
54213471	END SECTIONS 36"	EACH	2
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTION, 30"	EACH	1
54248510	CONCRETE COLLAR	CU YD	0.37
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1593
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	172
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15637
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	540
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	35
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6525
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	172
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	35
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	15637
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	540
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	114
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	39