

SUMMARY OF QUANTITIES

STP FUNDING
100% STATE
CONSTRUCTION TYPE CODE
SFTY-2A
PULASKI
SN 077-0001 & 077-0002

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
40600010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	60
40001300	PROTECTIVE COAT	50 YD	7764
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	569
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	7515
48203100	HOT-MIX ASPHALT SHOULDERS	TON	48
50102400	CONCRETE REMOVAL	CU YD	493.3
50157300	PROTECTIVE SHIELD	SQ YD	392
50300255	CONCRETE SUPERSTRUCTURE	CU YD	548
50300260	BRIDGE DECK GROOVING	SQ YD	6865
50300300	PROTECTIVE COAT	50 YD	7704
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	106580
50800515	BAR SPLICERS	EACH	596
52000110	PREFORMED JOINT STRIP SEAL	FOOT	1293
64200105	SHOULDER RUMBLE STRIP	FOOT	1280
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	10
67100100	MOBILIZATION	L SUM	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	210
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6005
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2072
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2575
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2575
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	6005
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	28
78300100	PAVEMENT MARKING REMOVAL	SO FT	427
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	28
X0323644	PAVEMENT MARKING GROOVING	FOOT	6005
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	6526
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	6526

STP FUNDING
100% STATE
CONSTRUCTION TYPE CODE
SFTY-2A
PULASKI
SN 077-0001 & 077-0002

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1.4
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

* specialty items

FILE NAME =	USER NAME = halsteadw	DESIGNED -	REVISED -
c:\pwwork\pwwork\halsteadw\d0172093\077-0001-0002-sht-misc.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 // IN.	CHECKED -	REVISED -
	PLOT DATE = 2/24/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF SHEETS STA. TO STA.

Rev. 5-25-10

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	D9 BSMART 2010-2	PULASKI	14	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 78174	