



NOTES:  
\* Field Verify (Match Existing)

**BILL OF MATERIAL (BOTH JOINTS)**

Bar	No.	Size	Length	Shape
a <sub>2</sub> (E)	20	#6	4'-0"	—
a <sub>7</sub> (E)	18	#7	16'-5"	—
a <sub>8</sub> (E)	40	#6	6'-6"	—
a <sub>10</sub> (E)	18	#7	18'-5"	—
d(E)	20	#5	4'-5"	J
d <sub>1</sub> (E)	16	#5	3'-3"	J
h(E)	6	#5	16'-5"	—
h <sub>2</sub> (E)	6	#5	18'-5"	—
x <sub>1</sub> (E)	112	#6	7'-1"	—
Concrete Superstructure			Cu. Yd.	20.5
Concrete Removal			Cu. Yd.	18.6
Reinforcement Bars, Epoxy Coated			Pound	3350

Reinforcement bars designated (E) shall be epoxy coated.  
**SOUTH ABUTMENT**  
**JOINT REPLACEMENT DETAILS**  
**PULASKI COUNTY**  
**STRUCTURE NO. 077-0001 (N.B.)**  
**STRUCTURE NO. 077-0002 (S.B.)**

