

# GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL		GUARDRAIL MARKERS		TERMINAL MARKERS DIRECT APPLIED EACH	COMMENTS
		TY 1, SPL (TAN) EACH	TYPE 2 EACH	AMBER EACH	SILVER EACH		
<b>EASTBOUND</b>							
5490+07.5 TO 5490+57.50		1		6		1	SN 097-0041
5490+57.5 TO 5494+95.00	437.50		1				SN 097-0041
<b>EASTBOUND TOTALS</b>	<b>437.50</b>	<b>1</b>	<b>1</b>	<b>6</b>	<b>0</b>	<b>1</b>	

LOCATION STATION TO STATION	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL		GUARDRAIL MARKERS		TERMINAL MARKERS DIRECT APPLIED EACH	COMMENTS
		TY 1, SPL (TAN) EACH	TYPE 2 EACH	AMBER EACH	SILVER EACH		
<b>WESTBOUND</b>							
5494+95.0 TO 5499+32.50	437.50		1	6			SN 097-0041
5499+32.5 TO 5499+82.50		1				1	SN 097-0041
<b>WESTBOUND TOTALS</b>	<b>437.50</b>	<b>1</b>	<b>1</b>	<b>6</b>	<b>0</b>	<b>1</b>	
<b>PROJECT TOTALS</b>	<b>875.00</b>	<b>2</b>	<b>2</b>	<b>12</b>	<b>0</b>	<b>2</b>	

# DRAINAGE SCHEDULE

STRUCTURE NUMBER	STATION TO STATION	PIPE CULVERTS, CLASS A, TYPE 1 24"	PRECAST REINFORCED CONCRETE FLARED ENDSECTIONS 24"	PIPE CULVERTS, CLASS A, TYPE 1 18"	PRECAST REINFORCED CONCRETE FLARED ENDSECTIONS 18"	INLET AND PIPE PROTECTION
		FOOT	EACH	FOOT	EACH	EACH
<b>WHITE COUNTY</b>						
097-0045	5263+75.0 TO 526675	300	2			1
	<b>WHITE COUNTY TOTALS</b>	<b>300</b>	<b>2</b>	<b>0</b>	<b>0</b>	<b>1</b>
<b>JEFFERSON COUNTY</b>						
041-0064	3407+75.0 TO 3410+75.0	300	2.00			1
041-0065	3285+50.0 TO 3286+00.0			50	2	1
041-0066	2823+25.0 TO 2826+75.0			350	2	1
041-0079	2264+50 TO 2267+50			330	2	1
041-0062	2856+00.0 TO 2858+75			330	2	1
	<b>JEFFERSON COUNTY TOTALS</b>	<b>300</b>	<b>2</b>	<b>1060</b>	<b>8</b>	<b>5</b>
	<b>TOTALS</b>	<b>600</b>	<b>4</b>	<b>1060</b>	<b>8</b>	<b>6</b>