

EROSION CONTROL

LOCATION STATION TO STATION	EROSION CONTROL BLANKET	PERIMETER EROSION BARRIER	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	REMARKS
	SQ YD	FOOT	FOOT	EACH	
IL 13 (CENTER)					
RT. STA 1793+58.20 TO STA 1799+08	125				
RT. STA 1779+43.50 TO STA 1788+50.50	2372				
RT. STA 1793+60.80 TO STA 1799+08		563			
RT. STA 1783+45.44 TO STA 1783+98.50		54			
RT. STA 1777+95 TO STA 1790+76			72		
RT. STA 1793+00 TO STA 1799+08			108		
STA 1783+95.30				1	
STA 1779+26.66				1	
HALFWAY ROAD					
STA 406+45				1	
RAMP A					
RT. STA 19+91.58 TO STA 27+00	1544				
LT. STA 19+91.58 TO STA 116+50	5196				
RT. STA 27+50 TO STA 40+50	1926				
LT. STA 19+91.58 TO STA 22+50		275			
LT. STA 23+00 TO STA 24+50			24		
LT. STA 24+86 TO STA 43+00			252		
RT. STA 21+00 TO STA 27+00			96		
RT. STA 27+50 TO STA 39+00			180		
STA 14+86				1	
STA 39+90				1	
RAMP G					
LT. STA 111+00 TO STA 112+50	37				
RT. STA 114+00 TO STA 142+00	7623				
RT. STA 148+50 TO STA 153+50	1057				
RT. STA 110+50 TO STA 119+50		890			
RT. STA 142+00 TO STA 148+50		710			
LT. STA 111+00			12		
RT. STA 113+00			12		
RT. STA 115+00 TO STA 118+00			48		
RT. STA 122+50 TO STA 141+50			252		
RT. STA 149+00 TO STA 154+00			24		
STA 110+50				1	
PROJECT TOTALS					
	19880	2492	1080	6	

SEEDING

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
IL 13 (EB)								
LT. STA 1787+50 TO STA 1788+00	2	0.02	0.02	2.6	1.8	1.8	0.04	0.04
RT. STA 1778+00 TO STA 1799+08	146	1.46	1.46	189.8	131.4	131.4	2.92	2.43
RAMP A								
LT. STA 20+50 TO STA 43+25	135	1.35	1.35	175.5	121.5	121.5	2.70	1.63
RT. STA 19+91.58 TO STA 40+50	131	1.31	1.31	170.3	117.9	117.9	2.62	1.90
RAMP G								
LT. STA 111+00 TO STA 120+50	19	0.19	0.19	24.7	17.1	17.1	0.38	0.37
RT. STA 111+00 TO STA 156+01	314	3.14	3.14	408.2	282.6	282.6	6.28	4.49
PROJECT TOTAL								
	747	7.47	7.47	971.1	672.3	672.3	14.94	10.86

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EROSION CONTROL AND SEEDING SCHEDULES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	*	(X1-6-2)K-1/2(1X-1)R-4	WILLIAMSON	194	37
		PLOT SCALE = #SCALE#	REVISED -		* I-57/IL 13 (FAI 57/FAP 331) CONTRACT NO. 78194								
		PLOT DATE = #DATE#	REVISED -		ILLINOIS FED. AID PROJECT								