

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY		Y060	RETAINING WALL Y007
				J000-2A	MULTI-USE PATHWAY SFTY - 1B		
100% STATE	STATE / CITY	100%					
* M7800620	EPOXY PAVEMENT MARKING - LINE 200MM	METER	338	338			
* M7800625	EPOXY PAVEMENT MARKING - LINE 300MM	METER	232	232			
M7830100	PAVEMENT MARKING REMOVAL	SQ M	185	185			
MX030199	TEMPORARY PAVEMENT	SQ M	2,920	2,920			
MX030396	FILL EXISTING STORM SEWERS	CUM	2	2			
MX030431	STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 1, 300MM	METER	138	138			
MX030457	STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 1, 375MM	METER	19	19			
MX030471	FORM LINER LIMESTONE SURFACE	SQ M	1,400				1,400
* MX033445	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CUM	1,702				1,702
MX501020	CONCRETE RETAINING WALL REMOVAL, VARIABLE HEIGHT	CUM	16	16			
MX550161	TEMPORARY STORM SEWER 300MM	METER	23	23			
MX602750	INLET-MANHOLE, TYPE G-1, 1.2M DIAMETER	EACH	5	5			
MX602751	INLET-MANHOLE, TYPE G-1, 1.2M DIAMETER, SPECIAL	EACH	33	33			
MX602755	INLET-MANHOLE, TYPE G-1, 1.5M DIAMETER	EACH	2	2			
MX602756	INLET-MANHOLE, TYPE G-1, 1.5M DIAMETER, SPECIAL	EACH	20	20			
MX030586	INLET-MANHOLE, TYPE G-1, 1.8M DIAMETER, SPECIAL	EACH	4	4			
MX720100	TEMPORARY SIGN PANEL ASSEMBLY	SQ M	10	10			
MZ022800	FENCE REMOVAL	METER	103	103			
MX032529	SEGMENTAL CONCRETE BLOCK WALL	SQ M	69	69			
X0323236	TEMPORARY INLET	EACH	5	5			
X0323959	FORM LINER MOCKUP	EACH	1				1
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	16	16			
X0323907	COMMUNICATIONS VAULT	EACH	14	14			



FUND CODE
 Y035-ITS

* SPECIALTY ITEM

REVISED