

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36R-1,37R-2	TAZEWELL	449	8
STA 7+663.000		TO STA 9+899.166		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY		Y060	RETAINING WALL Y007
				J000-2A	MULTI-USE PATHWAY SFTY - 1B		
				100% STATE	STATE / CITY	100%	
					90% / 10%		
M2011700	SUPPLEMENTAL WATERING	UNIT	720	720			
M2020010	EARTH EXCAVATION	CUM	26,288	26,288			
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CUM	1,086	1,086			
M2080150	TRENCH BACKFILL	CUM	5,312	5,312			
M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SQM	22,095	22,095			
* M2140100	GRADING AND SHAPING DITCHES	METER	91	91			
* M2500210	SEEDING, CLASS 2A	HA	1.25	1.25			
* M2500400	NITROGEN FERTILIZER NUTRIENT	KG	190	190			
* M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	190	190			
* M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	190	190			
* M2510115	MULCH, METHOD 2	HA	1.25	1.25			
* M2510635	HEAVY DUTY EROSION CONTROL BLANKET	SQM	2,240	2,240			
* M2520110	SODDING, SALT TOLERANT	SQM	10,287	10,287			
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	976	976			
M2800305	TEMPORARY DITCH CHECKS	METER	120	120			
M2800400	PERIMETER EROSION BARRIER	METER	2,086	2,086			
M2810125	STONE RIPRAP, CLASS B3	SQM	1,196	1,196			
M2820200	FILTER FABRIC	SQM	1,597	1,597			
M2850100	FABRIC FORMED CONCRETE REVETMENT MAT	SQM	19	19			
M3110300	SUB-BASE GRANULAR MATERIAL, TYPE A 300MM	SQM	48,730	48,730			
M3511200	AGGREGATE BASE COURSE, TYPE B 200MM	SQM	1,176	1,176			
M3550450	HOT-MIX ASPHALT BASE COURSE, 150MM	SQM	1,764	1,764			
M3550500	HOT-MIX ASPHALT BASE COURSE, 200MM	SQM	801	801			