F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36R-1,37R-2	TAZEWELL	449	34
STA 7+663.000		TO STA 10+097.000		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

LOCATION			STORM SEWER, CLASS A, TYPE 1					STORM SEWERS, CLASS A, TYPE 2						STORM SEWERS, CLASS A, TYPE 3				STORM SEWERS (WATER MAIN REQUIREMENTS)										PIPE CULVERTS, CLASS A TYPE 1, 450MM	TRENCH BACKFILL (CU YD)	SLOPE (%)
																		TYPE 1			TYPE 2					TYPE 3			
	FROM STR.	TO STR.	300MM	375MM	450MM	600MM	750MM	300MM	375MM	450MM	600MM	750MM	900MM	450MM	600MM	750MM	1200MM	300MM	375MM	450MM	300MM	375MM	450MM	600MM	750MM	375MM			
Sta 9+225 to Sta 9+400	119	121			29.7																							20.90	0.30
	44	121																18.9										10.61	0.78
	44	44A	1.2																									0.24	8.00
	45	46																									10.0	7.10	0.80
	121	122				29.1																						24.99	0.30
	122	123	6.4																									0.00	0.30
	122	124									22.0																	22.02	0.30
	47	124																			18.2							8.34	1.00
	124	125	5.3																									0.00	0.30
	124	126									18.5																	21.14	0.31
	126	127						5.3																				2.54	0.47
	126	128									28.2																	43.54	0.31
	128	129						5.2																				1.63	1.15
	48	128																							21.9			55.57	0.38
	48	49										7.2																0.00	0.50
	128	131											25.7															44.98	0.21
Sta 9+400 to Sta 9+675	130	131						8.1																				3.21	0.85
	131	132											13.5															25.08	0.20
	132	133											16.0															21.50	0.21
	51	133																			24.4							8.03	3.00
	133	134					18.0																					9.26	0.29
	134	135					18.3																					6.76	0.30
	135	136					32.9																					8.68	0.30
	136	137	5.0																									3.17	0.44
	136	138					23.1																					11.00	0.50
	138	139		4.2																								2.45	0.90
	52	139																	19.4									9.15	1.50
	52	53																60.3										20.05	1.00
	138	140					27.8																					13.28	0.50
	140	141	7.1																									4.54	2.94
	140	142										37.7																0.00	0.53
Sta 9+575 to Sta 9+750	142	143										43.3																20.07	1.32
	143	144						3.8																				2.50	2.25
	54	144																18.3										14.19	1.98
	143	145									68.7																	59.97	2.00
	145	148								3.9																		5.26	1.94
	148	147							12.0																			5.02	2.08
	147	147A	1.2																									0.34	8.00
	147	146	9.4																									7.76	0.73
	146	146A	1.2																									0.24	8.00
	55	145						18.4																				35.24	0.50
	145	149								48.7																		57.53	2.46
Sta 9+750 to Sta 9+925	149	150		3.4																								2.51	0.47
	149	151							23.8																			24.50	2.52
	56	151						18.4																				13.54	0.50
	151	152						70.8																				66.83	1.18
	57	152						18.4																				13.44	1.27
	152	153						20.7																				13.55	0.49
SUNRISE AVENUE	143	157	34.4																									4.75	2.01
	157	156	15.7																									6.30	2.04
	156	155	16.9																									5.82	1.96
	155	154	21.6																									5.79	2.36
SUB-TOTAL			125.4	7.6	29.7	29.1	120.1	169.1	35.8	52.6	137.4	88.2	55.2	0	0	0	0	97.5	19.4	0	42.6	0	0	0	21.9	0	10.0	1,025.81	
SUB-TOTAL SHEET #32			59.1	37.4	343.5	204.7	0	4.4	17.9	251.8	359.4	0	0	0	49.3	0	0	3.5	0	135.8	0	0	131.0	0	0	0	0	1,445.74	
SUB-TOTAL SHEET #33			118.5	95.4	90.2	0	0	331.2	44.4	223.6	139.7	74.7	0	168.8	0	19.5	9.0	36.8	0	0	48.8	51.5	73.2	58.4	0	49.2	0	2,751.29	
TOTAL QUANTITIES			303.0	140.4	463.4	233.8	120.1	504.7	98.1	528.0	636.5	162.9	55.2	168.8	49.3	19.5	9.0	137.8	19.4	135.8	91.4	51.5	204.2	58.4	21.9	49.2	10.0	4,972.00	
			M5500030	M5500040	M5500050	M5500065	M5500075	M5500430	M5500440	M5500450	M5500465	M5500475	M5500485	M5500850	M5500865	M5500875	M5500900	MX030431	MX030457	*4002002	*4001986	*4001987	*4001989	*4001990	*4001991	*4001988	M542H030	M2080150		

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 8 - SEGMENT 2

DRAINAGE SCHEDULE OF QUANTITIES - 8

SCALE: NTS DRAWN BY: RDT

DATE: DECEMBER 2003 CHECKED BY: