

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36R-1,37R-2	TAZEWELL	449	122
STA 7+663.000		TO STA 10+097.000		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

DRAINAGE AND UTILITIES GENERAL NOTES:

1. EXISTING MANHOLE / CATCH BASIN RIMS SHALL BE ADJUSTED AS NOTED.
2. ALL SEWER AND WATERMAIN CROSSINGS SHALL MEET WITH THE APPLICABLE LOCAL AND STATE GUIDELINES AS DESCRIBED IN THE LATEST EDITION OF THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS.
3. THE CONTRACTOR SHALL COORDINATE THE PROPOSED STORM SEWER CONSTRUCTION WITH ALL OTHER UTILITY ADJUSTMENTS AND INSTALLATIONS AS APPROVED BY THE ENGINEER.
4. UNDERGROUND UTILITIES AND DRAINAGE SYSTEMS SHOWN ON THE PLANS ARE BASED ON AVAILABLE SURVEYS AND AS-BUILT INFORMATION. THE LOCATION OF UNDERGROUND FACILITIES ARE APPROXIMATE. PRIOR TO CONSTRUCTION, THE CONTRACTOR IS REQUIRED TO VERIFY ALL UTILITY LOCATION AND DEPTHS.
5. ALL ADJUSTMENTS OF CORPORATION STOPS, METERS OR OTHER DEVICES ENCOUNTERED ON SERVICE LINES SHALL BE BY OTHERS.
6. THE CONTRACTOR SHALL OUTLET LONGITUDINAL FABRIC LINED TRENCH PIPE UNDERDRAIN USING PIPE UNDERDRAINS (SPECIAL) TO CONNECT TO STORM SEWER STRUCTURES AS INDICATED ON THE SCHEDULES. PROPER PIPE OPENINGS SHALL BE PROVIDED FOR EACH OF THE AFFECTED STORM SEWER STRUCTURES. THIS WORK SHALL BE INCLUDED IN THE COST FOR THE RESPECTIVE STORM SEWER STRUCTURE.
7. DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN ALL SURFACE DRAINAGE WITHIN THE PROJECT LIMITS. ALL STORM FLOW MUST BE MAINTAINED AT ALL TIMES, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
8. ANY EXISTING DRAINAGE FACILITIES DISTURBED OR DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT HIS/HER EXPENSE. THIS WORK SHALL MEET WITH THE SATISFACTION OF THE ENGINEER.
9. ALL STORM SEWER IS RCP UNLESS OTHERWISE SPECIFIED.

DRAINAGE AND UTILITIES LEGEND:

EXISTING STORM SEWER		FRAME AND LID TO BE ADJUSTED	(A)
EXISTING SANITARY		ITEM TO BE ADJUSTED	(ADJ)
EXISTING CULVERT		ITEM TO BE RELOCATED	(REL)
EXISTING DITCH		ITEM TO BE REMOVED	(R)
EXISTING CATCH BASIN		ITEM TO BE RECONSTRUCTED	(REC)
EXISTING INLET		WATER ITEM TO BE ADJUSTED	(A)
EXISTING MANHOLE			
EXISTING FLARED END SECTION			
EXISTING HEADWALL			
PROPOSED STORM SEWER			
PROPOSED FABRIC LINED TRENCH UNDERDRAIN			
PROPOSED DITCH			
PROPOSED INLET			
PROPOSED MANHOLE			
PROPOSED FLARED END SECTION			
PROPOSED SWALE			
PROPOSED INLET-MANHOLE			

NOTE: BOXED ITEMS INDICATE WORK NOT PAID FOR SEPARATELY, BUT INCLUDED AS PART OF ANOTHER PAY ITEM OR COST ASSOCIATED WITH THE CONTRACT.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 8 - SEGMENT 2 DRAINAGE NOTES
NAME	DATE	

SCALE: NTS
DATE: DECEMBER, 2003

DRAWN BY: RDT
CHECKED BY: SAE