

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				70% FED 30% STATE (IL RT 8) J000-2A	70% FED 30% CITY (SUMMIT) 20	70% FED 21% STATE 9% CITY (DRAINAGE) 1000-1A	70% FED 15% STATE 15% CITY (SIGNALS) Y031-1F	70% FED 15% STATE 15% CITY (SIDEWALK) SFTY 1-B
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	20					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	80	80				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	240	240				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	194	194				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13,202	13,202				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	833	833				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	170	170				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	230	230				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5780	5780				
72000200	* SIGN PANEL - TYPE 2	SO FT	52	52				
78000100	* THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	9		9			
78000200	* THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,666		10,666			
78000500	* THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	145		145			
78000600	* THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	342		342			
78001100	* PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	35	35				
78001110	* PAINT PAVEMENT MARKING - LINE 4"	FOOT	1538	1538				
78001140	* PAINT PAVEMENT MARKING - LINE 8"	FOOT	318	318				
78001150	* PAINT PAVEMENT MARKING - LINE 12"	FOOT	393	393				
78003130	* PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	360	360				
78005100	* EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	165	165				
78005110	* EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3594	3594				
78005140	* EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1829	1829				
78005150	* EPOXY PAVEMENT MARKING - LINE 12"	FOOT	90	90				
78005180	* EPOXY PAVEMENT MARKING - LINE 24"	FOOT	168	168				
78100100	* RAISED REFLECTIVE PAVEMENT MARKER	EACH	103	103				
78300200	* RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	30	30				
80500200	* SERVICE INSTALLATION, TYPE B	EACH	1				1	
81012600	* CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	795				795	
81012800	* CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	277				277	
81012900	* CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	166				166	
81306500	* REMOVE EXISTING JUNCTION BOX	EACH	3				3	
81400700	* HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5				5	
81400720	* DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1				1	
81702130	* ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 1/C NO. 6	FOOT	935				935	
81900200	* TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1238				1238	
82102400	* LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4				4	
84400105	* RELOCATE EXISTING LIGHTING UNIT	EACH	2				2	
85700205	* FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1				1	
87301245	* ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	1689				1689	

* SPECIALTY ITEM

FILE NAME =
PLOT SCALE = #SCALE#
PLOT DATE = #DATE#
PLOT TIME = #TIME#

DESIGNED - RAW
DRAWN - RAW
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -



SUMMARY OF QUANTITIES
SCALE: SHEET NO. 4 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6775	04-00141-00-FP	TAZEWELL	187	5
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 89352	