

THERMOPLASTIC PAVEMENT MARKING - LINE 4"						
LOCATION STATION TO STATION		DESCRIPTION	NUMBER OF STRIPES	78000200 FOOT		
SOUTH SUMMIT DRIVE						
STA. 107+95.44	TO	STA. 111+13.41	APPROACH TAPER	4	1226.5	
STA. 111+13.41	TO	STA. 112+89.40	LEFT TURN LANE TAPER	4	692.6	
STA. 112+89.40	TO	STA. 113+22.93	CL TO PCC PAVEMENT	2	67.1	
NORTH SUMMIT DRIVE						
STA. 11+95.91	TO	STA. 12+04.59	PCC PAVEMENT TO CL	2	17.4	
STA. 12+04.59	TO	STA. 13+79.58	LEFT TURN LANE TAPER	4	684.74	
STA. 13+79.58	TO	STA. 15+64.60	APPROACH TAPER	4	707.11	
STA. 15+64.60	TO	STA. 18+00.00	CL STRIPE	2	470.8	
STA. 18+00.00	TO	STA. 24+00.00	CL STRIPE	2	1200	
STA. 24+00.00	TO	STA. 30+00.00	CL STRIPE	2	1200	
STA. 30+00.00	TO	STA. 36+00.00	CL STRIPE	2	1200	
STA. 36+00.00	TO	STA. 42+00.00	CL STRIPE	2	1200	
STA. 42+00.00	TO	STA. 48+00.00	CL STRIPE	2	1200	
STA. 48+00.00	TO	STA. 52+00.00	CL STRIPE	2	800	
				TOTAL	10,666	

THERMOPLASTIC PAVEMENT MARKING - LINE 8"				
LOCATION STATION TO STATION		DESCRIPTION	NUMBER OF STRIPES	78000500 FOOT
SOUTH SUMMIT DRIVE				
STA. 112+87.40	TO	STA. 113+22.93	OFFSET LT TURN LANE LINE	2
STA. 113+21.43	TO	STA. 113+22.93	RT TURN LANE LINE	1
NORTH SUMMIT DRIVE				
STA. 11+95.91	TO	STA. 12+06.58	OFFSET LT TURN LANE LINE	2
STA. 11+95.91	TO	STA. 12+42.55	OFFSET LT TURN LANE LINE	1
				TOTAL
				145

THERMOPLASTIC PAVEMENT MARKING - LINE 12"			
LOCATION STATION TO STATION		DESCRIPTION	78000600 FOOT
SOUTH SUMMIT DRIVE			
STA. 108+30.59	TO	STA. 112+66.84	TAPER MEDIAN STRIPES - 15' ON CENTERS
STA. 112+92.36			LT TURN OFFSET CHEVRONS
STA. 113+12.38			LT TURN OFFSET CHEVRONS
NORTH SUMMIT DRIVE			
STA. 12+34.90	TO	STA. 15+28.19	TAPER MEDIAN STRIPES - 15' ON CENTERS
STA. 51+99			WEST RADIUS RETURN AT CENTENNIAL DRIVE
STA. 52+18			WEST RADIUS RETURN AT CENTENNIAL DRIVE
STA. 52+27			WEST RADIUS RETURN AT CENTENNIAL DRIVE
STA. 52+03			EAST RADIUS RETURN AT CENTENNIAL DRIVE
STA. 52+18			EAST RADIUS RETURN AT CENTENNIAL DRIVE
STA. 52+26			EAST RADIUS RETURN AT CENTENNIAL DRIVE
			TOTAL
			342

PAINT PAVEMENT MARKING - LINE 4"							
LOCATION STATION TO STATION		LT/RT	DESCRIPTION	LENGTH FOOT	SPACING FOOT	NUMBER OF STRIPES PER	78001110 LENGTH OF FOOT
FROM STA 193+39.62	TO STA 196+40.51	RT	SOLID WHITE LINE	336.03		1	336
FROM STA 197+11.22	TO STA 199+77.07	RT	SOLID WHITE LINE	301.81		1	302
FROM STA 200+58.20	TO STA 204+60	RT	SOLID WHITE LINE	409.38		1	409
FROM STA 200+86.87	TO STA 204+60	LT	SOLID WHITE LINE	490.74		1	491
							TOTAL
							1538

PAINT PAVEMENT MARKING - LINE 8"							
LOCATION STATION TO STATION		RT/LT	DESCRIPTION	LENGTH FOOT	SPACING FOOT	NUMBER OF STRIPES PER	78001140 LENGTH OF FOOT
FROM STA 197+11.22	TO STA 198+53.40	RT	WHITE SKIP DASH LINE	148	9	17	51.00
FROM STA 198+53.40	TO STA 199+49	RT	WHITE SOLID LINE	95.6		1	95.6
FROM STA 201+12.92	TO STA 202+17.94	LT	WHITE SOLID LINE	105.02		1	105.02
FROM STA 202+17.94	TO STA 204+10	LT	WHITE SKIP DASH LINE	192.06	9	22	66.00
							TOTAL
							318

PAINT PAVEMENT MARKING - LINE 12"				
LOCATION STATION TO STATION		LT/RT	DESCRIPTION	78001150 FOOT
FROM STA 193+39.62	TO STA 196+40.51	RT	WHITE DIAGONAL LINE	121.25
FROM STA 197+11.22	TO STA 199+77.07	RT	WHITE DIAGONAL LINE	165.00
FROM STA 200+58.20	TO STA 201+45.36	RT	WHITE DIAGONAL LINE	50.42
FROM STA 200+78.88	TO STA 201+30.13	LT	WHITE DIAGONAL LINE	56.19
				TOTAL
				393

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		
LOCATION STATION	DESCRIPTION	78000100 SO FT
SOUTH SUMMIT DRIVE		
STA. 113+17.75	LEFT TURN ARROW - SMALL	8.8
		TOTAL
		9

PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS		
LOCATION STATION	DESCRIPTION	78001100 SO FT
RT STA 198+68.42	RIGHT TURN ARROW - SMALL	8.8
RT STA 199+40.08	RIGHT TURN ARROW - SMALL	8.8
LT STA 201+37.79	LEFT TURN ARROW - SMALL	8.8
LT STA 202+13.11	LEFT TURN ARROW - SMALL	8.8
		TOTAL
		35