

EPOXY PAVEMENT MARKING - LINE 4"							
LOCATION STATION TO STATION	LT/RT	DESCRIPTION	LENGTH	SPACING	NUMBER OF STRIPES	LENGTH OF LINE	78005110
			FOOT	FOOT	PER LENGTH	FOOT	FOOT
IL ROUTE 8							
FROM STA 189+37 TO STA 197+68.89	RT	YELLOW SOLID LINE	831.89		1		832
FROM STA 189+37 TO STA 197+68.89	LT	YELLOW SOLID LINE	831.89		1		832
FROM STA 189+37 TO STA 194+84.89	LT	YELLOW SKIP DASH LINE	547.89	40	14	10	140
FROM STA 189+37 TO STA 194+84.89	RT	YELLOW SKIP DASH LINE	547.89	40	14	10	140
FROM STA 196+16.19 TO STA 197+68.89	LT	YELLOW SKIP DASH LINE	152.7	40	4	10	40
FROM STA 196+16.19 TO STA 197+68.89	RT	YELLOW SKIP DASH LINE	152.7	40	4	10	40
FROM STA 197+68.89 TO STA 199+49.00	LT	DOUBLE YELLOW LINE	180.11		2		360
FROM STA 201+12.92 TO STA 203+05.00	RT	DOUBLE YELLOW LINE	192.08		2		384
FROM STA 203+05.00 TO STA 204+60.00	LT	YELLOW SOLID LINE	155		1		155
FROM STA 203+05.00 TO STA 204+60.00	RT	YELLOW SOLID LINE	155		1		155
FROM STA 203+05.00 TO STA 204+60.00	LT	YELLOW SKIP DASH LINE	155	40	4	10	40
FROM STA 203+05.00 TO STA 204+60.00	RT	YELLOW SKIP DASH LINE	155	40	4	10	40
FROM STA 113+22.93 TO STA 114+22.43	LT	DOUBLE YELLOW LINE	99.5		2		199
FROM STA 10+77.50 TO STA 11+95.96	RT	DOUBLE YELLOW LINE	118.46		2		237
TOTAL							3594

RAISED REFLECTIVE PAVEMENT MARKERS 78100100				
LOCATION STATION TO STATION	LT/RT	ONE WAY (CRYSTAL) EACH	TWO WAY (AMBER) EACH	ONE WAY (AMBER) EACH
STA 189+37 TO STA 199+49	LT	13		
STA 189+37 TO STA 193+40	RT	5		
STA 189+37 TO STA 197+68.49	LT		21	
STA 189+37 TO STA 197+68.49	RT		21	
STA 197+68.89 TO STA 199+49	LT		10	
STA 201+12.92 TO STA 203+05	RT		10	
STA 201+12.92 TO STA 203+05	LT	6		
STA 198+43.00 TO STA 199+49	RT	6		
STA 201+12.92 TO STA 202+17.94	RT	3		
STA 203+05 TO STA 204+60	LT		4	
STA 203+05 TO STA 204+60	RT		4	
SUB-TOTAL		33	70	0
TOTAL				103

EPOXY PAVEMENT MARKING - LINE 8"			
LOCATION STATION TO STATION	LT/RT	DESCRIPTION	78005140 FOOT
STA 199+57.94		WHITE SOLID LINE - CROSSWALK	173.04
STA 10+60 (N. Summit)		WHITE SOLID LINE - CROSSWALK	190.62
STA 201+00.00		WHITE SOLID LINE - CROSSWALK	183.50
STA 113+83.66 (S. Summit)		WHITE SOLID LINE - CROSSWALK	174.00
FROM STA 198+43.00 TO STA 199+49.00	RT	WHITE SOLID LINE	215.14
FROM STA 201+12.92 TO STA 202+31.00	LT	WHITE SOLID LINE	239.30
FROM STA 10+77.50 TO STA 11+95.96	LT	WHITE SOLID LINE	236.92
FROM STA 10+77.50 TO STA 11+95.96	LT	WHITE SOLID LINE	118.46
FROM STA 113+22.93 TO STA 114+22.43	RT	WHITE SOLID LINE	199.00
FROM STA 113+22.93 TO STA 114+22.43	RT	WHITE SOLID LINE	99.50
TOTAL			1829

EPOXY PAVEMENT MARKING - LINE 12"						
LOCATION STATION TO STATION	DESCRIPTION	LENGTH FOOT	SPACING FOOT	NUMBER OF CHEVRONS	LENGTH OF FOOT	78005150 FOOT
FROM STA 198+43.00 TO STA 199+49.00	CHEVRONS	106	20	5	2.74	13.7
FROM STA 201+12.92 TO STA 202+31.00	CHEVRONS	118.08	20	6	2.74	16.44
FROM STA 10+77.50 TO STA 11+95.96	CHEVRONS	118.46	20	6	6	36
FROM STA 113+22.93 TO STA 114+22.43	CHEVRONS	99.50	20	4	6	24
TOTAL						90

EPOXY PAVEMENT MARKING - LINE 24"		
LOCATION STATION	DESCRIPTION	78005180 FOOT
STA 199+49	STOP BAR	44.24
STA 201+07.61	STOP BAR	43.70
STA 114+22.43	STOP BAR	39.68
STA 10+77.50	STOP BAR	40.50
TOTAL		168

EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS 78005100 SQ FT		
LOCATION STATION	DESCRIPTION	78005100 SQ FT
IL ROUTE 8		
STA 190+50	RIGHT TURN ARROW - SMALL	8.8
STA 190+50	LEFT TURN ARROW - SMALL	8.8
STA 194+00	RIGHT TURN ARROW - SMALL	8.8
STA 194+00	LEFT TURN ARROW - SMALL	8.8
STA 197+37	RIGHT TURN ARROW - SMALL	8.8
STA 197+37	LEFT TURN ARROW - SMALL	8.8
STA 198+49.37	RIGHT TURN ARROW - SMALL	8.8
STA 199+39.38	RIGHT TURN ARROW - SMALL	8.8
STA 201+37.37	LEFT TURN ARROW - SMALL	8.8
STA 202+13.11	LEFT TURN ARROW - SMALL	8.8
STA 11+00	RIGHT TURN ARROW - SMALL	8.8
STA 11+00	LEFT TURN ARROW - SMALL	8.8
STA 11+75	RIGHT TURN ARROW - SMALL	8.8
STA 11+75	LEFT TURN ARROW - SMALL	8.8
STA 10+95	THROUGH ARROW - SMALL	6.5
STA 113+34	LEFT TURN ARROW - SMALL	8.8
STA 113+34	RIGHT TURN ARROW - SMALL	8.8
STA 113+96	LEFT TURN ARROW - SMALL	8.8
STA 113+96	RIGHT TURN ARROW - SMALL	8.8
TOTAL		165

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	78300200 EACH
FROM STA 201+45.24 TO STA 204+60	30
TOTAL	30

FILE NAME :	PLOT SCALE = *SCALE*	DESIGNED -	REVISED -
	PLOT DATE = *DATE*	DRAWN -	REVISED -
	PLOT TIME = *TIME*	CHECKED -	REVISED -
		DATE -	REVISED -



SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 10 OF 14 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6775	04-00141-00-FP	TAZEWELL	187	27
CONTRACT NO. 89352				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				