

TABULATION OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	CONTRACT	SHEET NO.	TOTAL SHEETS
FAS 254	09-00024-00-RS	Putnam	89446	2	4

40600100 BITUMINOUS MATERIALS (PRIME COAT)

STATION	WIDTH	SQ. YD	QUANTITY REQUIRED
MAINLINE 0+11 TO 272+58	24'	72,659	7,265.9 GAL
TOWN 272+62 TO 286+00	22'-55'	5,133	513.3 GAL
SIDE ROADS (SEE PAGE 4)			153.0 GAL
MCNABB STREETS (SEE PAGE 3)			49.1 GAL
TERMINAL INTERSECTIONS (SEE PAGE 4)			<u>13.2 GAL</u>
			7994.5 GAL
RATE OF APPL = 0.1 GAL/SQ YD		TOTAL	7994.5 (USE 7995 GAL)

40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	QUANTITY REQUIRED
TERMINAL INTERSECTIONS (SEE PAGE 4)	33.5 TON
SIDE ROADS (SEE PAGE 4)	256.5 TON
MCNABB STREETS (SEE PAGE 3)	<u>41.2 TON</u>
	331.2 TON
RATE OF APPL = 112 LB./ S.Y./IN.	
TOTAL	331.2 (USE 332 TON)

40600300 AGGREGATE PRIME COAT

STATION	SQ YD	QUANTITY REQUIRED
0+11 TO 272+58	72,659	145.3 TON
272+62 TO 286+00	5,133	10.3 TON
SIDE ROADS	1530	3.0 TON
MCNABB STREETS	491	1.0 TON
TERMINAL INTERSECTON	132	<u>0.3 TON</u>
		159.9 TON
RATE OF APPL = 4 LB/SQ YD		TOTAL 159.9 (USE 160 TON)

40600625 LEVELING BINDER (MACHINE METHOD) N50

STATION	THICKNESS	SQ. YD	QUANTITY REQUIRED
0+11 TO 203+25	2"	54,170.70	6067.1 TON
212+00 TO 272+58	2"	16,154.70	1,809.3 TON
MAIL BOX TURNOUTS (SEE PAGE 4)			23.8 TON
ENTRANCES (SEE PAGE 4)			<u>96.5 TON</u>
			7996.7 TON
RATE OF APPL = 112 LBS/SQ YD-IN.		TOTAL	7996.7 (USE 7997 TON)

44000198 HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

LOCATION	LENGTH	WIDTH	QUANTITY REQUIRED
CURB & GUTTER	1,352	6"	<u>901.3 SQ YD</u>
			901.3 SQ YD
TOTAL			901 SQ YD

HMA BINDER COURSE, IL 9.5 N, 50

STATION	THICKNESS	SQ. YD	QUANTITY REQUIRED
0+11 TO 203+25	1 1/4"	54,170.70	3791.9 TON
212+00 TO 272+58	1 1/4"	16,154.70	<u>1130.8 TON</u>
			4922.7 TON
RATE OF APPL = 112 LBS/SQ YD-IN.		TOTAL	4922.7 (USE 4923 TON)

40600982 HOT MIX ASPHALT SURFACE REMOVAL, BUTT JOINT

LOCATION	LENGTH	WIDTH	QUANTITY REQUIRED
RR CROSSING 272+58	50'	21'	130.9 SQ YD
RR CROSSING 272+62	43'	27'	116.6 SQ YD
BRIDGE APPROACH 208+60	25'	22'	61.1 SQ YD
BRIDGE APPROACH 209+40	25'	22'	61.1 SQ YD
TERMINAL INTERSECTION (SEE PAGE 4)			677.8 SQ YD
SIDE ROADS (SEE PAGE 4)			199.8 SQ YD
MCNABB STREETS (SEE PAGE 3)			<u>196.6 SQ YD</u>
			1443.9 SQ YD
TOTAL			1443.9 (USE 1444 SQ YD)

40603310 HMA SURFACE COURSE MIX "C" N50

STATION	THICKNESS	SQ. YD	QUANTITY REQUIRED
0+11 TO 203+25	1 1/4"	54,171	3791.9 TON
203+25 TO 212+00	2"	2,333	261.3 TON
212+00 TO 272+58	1 1/4"	16,155	1130.8 TON
272+62 TO 286+00	1 1/2"	5,133	431.2 TON
MAIL BOX TURNOUTS (SEE PAGE 4)			29.4 TON
ENTRANCES (SEE PAGE 4)			<u>138.6 TON</u>
			5783.2 TON
RATE OF APPL = 112 LBS/SQ YD-IN.		TOTAL	5783.2 (USE 5784 TON)

78001110 PAINT PAVEMENT MARKING LINE - 4"

LOCATION	EDGE LINE	QUANTITY REQUIRED
Sta. 0+11 to 272+60	EDGE LINE	54298 FT
Sta. 280+54 to 286+00	EDGE LINE	1092 FT
Sta. 0+11 to 270+60	CENTERLINE	6762 FT
Sta. 270+60 to 286+00	DBL NO PASSING	3080 FT
WEST BOUND LANE	NO PASSING	7953 FT
EAST BOUND LANE	NO PASSING	<u>9041 FT</u>
		82226 FT
TOTAL		82226 FT (USE 82226)

48101200 AGGREGATE SHOULDER, TYPE B

STATION	THICKNESS	SQ. YD	QUANTITY REQUIRED
0+11 TO 203+25	4 1/2"	9,028	2347.4 TON
203+25 TO 212+00	2"	389	44.9 TON
212+00 TO 272+58	4 1/2"	2,692	700.0 TON
280+54 TO 286+00	1 1/2"	243	<u>21.0 TON</u>
			3113.3 TON
RATE OF APPL = 2.08 TON/CU YD		TOTAL	3113.3 (USE 3114 TON)

70300220 TEMPORARY PAVEMENT MARKING LINE - 4"

SEE PAINT PAVEMENT MARKING LINE - 4"	TOTAL	82226 FT.
--------------------------------------	-------	-----------