



PAVEMENT MARKING SCHEDULE									
LOCATION		THERMOPLASTIC PAVEMENT MARKINGS - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	PAINT PAVEMENT MARKING-LINE 4"	PAINT PAVEMENT MARKING-LINE 8"	PAINT PAVEMENT MARKING-LINE 12"
		SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
BEGIN STATION	END STATION								
BRIARWOOD LN. INTERSECTION									
85+26.41	86+86.68	31		50		21	444	218	103
LEXINGTON DR. INTERSECTION									
86+86.68	87+76.69	16	64	101			296	56	51
LEXINGTON DR. TO SHERIDAN RD.									
87+76.69	89+23.81	101	283	226			125	17	14
SHERIDAN & NORTHMOOR INTERSECTION									
89+23.81	92+40.00	377	716	1446	175	154			
SHERIDAN BEGIN TO NORTHMOOR									
249+25.00	251+76.14	83	366	82			344	188	44
NORTHMOOR RD. TO KELLAR PKWY.									
254+21.85	260+35.00	214	1798	972	122				
KELLAR PKWY. INTERSECTION TO END									
260+35.00	261+78.46	0	484		17				
MAINTENANCE OF TRAFFIC									
83+82.76	263+15.39	182	35362			353			
TOTAL		1004	39073	2877	314	528	1209	479	212

STORM SEWER END SECTION SCHEDULE		
LOCATION	PRECAST REINFORCED CONCRETE FLARED END SECTION 12" EACH	PRECAST REINFORCED CONCRETE FLARED END SECTION 15" EACH
CENTERLINE STATION		
NORTHMOOR RD. 82+42.67, 24.81' RT. 87+59.77, 43.60' LT.	1	1
SHERIDAN RD. 265+29.48, 26.68' RT.		1
TOTAL	1	2

STONE RIPRAP SCHEDULE		
LOCATION	STONE RIPRAP, CLASS A4	FILTER FABRIC
CENTERLINE STATION	TON	SQ YD
NORTHMOOR RD. 82+42.76, 32.19' RT.	13	21
NORTHMOOR RD. 85+16.99, 24.37' LT.	14	24
SHERIDAN ROAD 265+36.48, 26.59' RT.	13	22
TOTAL	40	67

EARTHWORK					
LOCATION		EARTH EXCAVATION	ADJUSTED EXCAVATION FOR SHRINKAGE (25%)	EMBANKMENT	FURNISHED EXCAVATION
		CU YD	CU YD	CU YD	CU YD
BEGIN STATION	END STATION				
BRIARWOOD LN. INTERSECTION					
85+26.41	86+86.68	376	282	260	-22
LEXINGTON DR. INTERSECTION					
86+86.68	87+76.69	506	379	152	-228
LEXINGTON DR. TO SHERIDAN RD.					
87+76.69	89+23.81	698	524	41	-483
SHERIDAN & NORTHMOOR INTERSECTION					
89+23.81	92+40.00	1836	1377	265	-1112
SHERIDAN BEGIN TO NORTHMOOR					
249+25.00	251+76.14	596	447	452	5
NORTHMOOR RD. TO KELLAR PKWY.					
254+21.85	260+35.00	2114	1585	731	-854
KELLAR PKWY. INTERSECTION TO END					
261+78.46	265+83.28	779	584	56	-528
TOTAL		6905	5179	1957	-3222

FILE NAME = I:\09Jobs\09L0027\CADD\Road\Sheet\c-68sch.dgn	USER NAME = Ander-00846	DESIGNED - RLA	REVISED -
PLOT SCALE = 5.0000' / in.	CHECKED - CAL	DRAWN - RLA	REVISED -
PLOT DATE = 03/19/10	DATE - 03/19/10	CHECKED - CAL	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6647	08-00302-00-TL	PEORIA	102	9
6595	09-00047-02-TL			

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT M-5093(138) CONTRACT NO. 89523