



- ① WHITE THERMOPLASTIC STOP BAR PAVEMENT MARKING LINE - 24" SOLID
- ② WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" SOLID
- ③ YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ④ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ⑤ YELLOW THERMOPLASTIC MARKING LINE - 10' LONG, 30' GAP - 4"
- ⑥ THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS (FOR LEFT AND RIGHT TURN LANE ONE ARROW 20' FROM FRONT OF STORAGE AND ONE ARROW 20' AT BACK OF STORAGE)
- ⑦ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" (2' LONG, 6' GAP)
- ⑧ DOUBLE YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID
- ⑨ YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID
- ⑩ WHITE PAINT PAVEMENT MARKING LINE - 8" SOLID
- ⑪ DOUBLE YELLOW PAINT PAVEMENT MARKING LINE - 4" SOLID
- ⑫ WHITE PAINT PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ⑬ YELLOW PAINT PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ⑭ WHITE PAINT PAVEMENT MARKING LINE - 8" (2' LONG, 6' GAP)

FILE NAME =	USER NAME = Ander-00846	DESIGNED - RLA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	NORTHMOOR RD. PAVEMENT MARKING PLAN	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
H:\09Jobs\09L0027\CA00\Road\Sheet\c-101\mk.dgn	DRAWN - RLA	REVISED -	6647			08-00302-00-TL	PEORIA	102	53	
PLOT SCALE = 20,0000 1/1 in.	CHECKED - CAL	REVISED -	6595			09-00047-02-TL	CONTRACT NO. 89523			
PLOT DATE = 03/19/10	DATE - 03/19/10	REVISED -	FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	M-5093138			

SCALE: 1"=20' SHEET NO. OF SHEETS STA. 85+26.42 TO STA. 88+00.00