


**KEYED NOTES:**

- 1 NEW 250W HPS LUMINAIRE MOUNTED ON NEW 40 FT. POLE.
- 2 2-1/C NO. 6, 600 XLP, 1-1/C NO. 6 G., 600 XLP, 2" PVC CONDUIT IN TRENCH.
- 3 NEW 400W HPS LUMINAIRE MOUNTED 45 FT. ABOVE FINISHED GRADE ON TRAFFIC SIGNAL POLE.
- 4 EXISTING CONTROLLER WITH 4 EXISTING 30A/2P CIRCUIT BREAKERS, SEE STAGE 3 DRAWINGS.
- 5 4-1/C NO. 6, 600 XLP, 1-1/C NO. 6 G., 600 XLP, 2" PVC CONDUIT IN TRENCH.



FILE NAME =	USER NAME = Ander20846	DESIGNED - PJG	REVISED -
I:\09Jobs\09L0027\CADD\Elec\Sheet\002.dgn		DRAWN - ANC	REVISED -
PLT SCALE = 20.0000' / in.		CHECKED - RDN	REVISED -
PLT DATE = 03/22/2010		DATE - 03/19/10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**LIGHTING PLAN  
NORTHMOOR AND SHERIDAN ROAD STAGE 1 IMPROVEMENT**

F.A.I.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6647	08-00302-00-PV	PEORIA	102	64
6595	09-00047-01-PV			

CONTRACT NO. 89523

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT M-5093(135)

SCALE: 1"=20' SHEET NO. 3 OF 10 SHEETS STA. 89+00 TO STA. 92+40