

## SCHEDULE OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 6576	09-00177-00-SP	PEORIA	33	3
FED. ROAD DIST. NO.	ILLINOIS PROJECT		HSP 5093 (151)	
	7			
CONTRACT NO. 89561				

### GUARDRAIL PAY ITEMS

LOCATION	SPB GUARDRAIL TY. A, 9' POST (FOOT)	SPB GUARDRAIL TY. B (FOOT)	TRAFFIC BARRIER TERMINAL, TY. 2 (EACH)	TRAFFIC BARRIER TERMINAL TY. 1 (SPECIAL) TANGENT (EACH)	SPB GUARDRAIL REMOVAL, TY. A (FOOT)	TRAFFIC BARRIER TERMINAL REMOVAL, TY. 1 (EACH)	TRAFFIC BARRIER TERMINAL REMOVAL, TY. BLR 19-1 (EACH)	MONO. GUARDRAIL REFLECTORS (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)	TRAFFIC BARRIER TERMINAL, TY. 1 (EACH)
STRUCTURE 072-3001 TO MILE 0.18	-	219	1	1	-	-	-	4	1	-
MILE 0.28 TO MILE 0.36	363	-	-	4	-	-	-	5	4	-
MILE 2.0 TO MILE 2.14	663	-	-	2	-	-	-	9	2	-
MILE 2.32 TO MILE 2.44	625	-	-	2	-	-	-	7	2	-
MILE 2.79 TO MILE 2.84	163	-	-	2	-	-	-	4	2	-
MILE 2.87 TO MILE 2.91	125	-	-	2	125	-	1	4	2	-
MILE 2.89 TO MILE 2.92	63	-	-	2	75	-	1	4	2	-
MILE 2.96 TO MILE 3.00	-	-	-	-	-	-	-	4	2	-
MILE 3.01 TO MILE 3.05	12.5	-	-	-	12.5	-	2	4	2	2
MILE 3.02 TO MILE 3.09	-	-	-	-	-	-	-	4	2	-
MILE 3.15 TO MILE 3.19	150	-	-	2	-	-	-	4	2	-
MILE 4.37 TO MILE 4.44	250	-	-	2	-	-	-	4	2	-
MILE 4.38 TO MILE 4.48	213	-	-	2	-	-	2	11	2	-
MILE 4.81 TO MILE 4.89	-	338	-	2	370	1	1	5	2	-
MILE 4.85 TO MILE 4.89	-	138	-	2	50	-	-	4	2	-
TOTALS =	2,628	695	1	25	633	1	7	77	31	2

NOTE: SHOULDER WIDENING FOR TRAFFIC BARRIER TERMINALS SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED TO BE INCLUDED IN THE COST OF THE VARIOUS TRAFFIC BARRIER TERMINAL PAY ITEMS.

### BRIDGE RAIL (SPECIAL)

LOCATION	FOOT
MILE 3.01 TO MILE 3.05	13
TOTAL =	13