

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 6576	09-00177-00-SP	PEORIA	33	8
FED. ROAD DIST. NO.	7	ILLINOIS	PROJECT: HSP 5093 (151)	
CONTRACT NO.	89561			

SIGN PANEL AND POST QUANTITIES
KICKAPOO CREEK ROAD (R51), SECTION 09-00177-00-SP, CONTRACT 89561
 START 0.00 MILES @ IL 8 IN POTTSTOWN
 END 5.00 MILES @ TREASURE STREET IN BARTONVILLE

BOLD ITEMS SIGNIFY NEW SIGN LOCATIONS

SIGN NUMBER	MILES FROM		EXISTING MESSAGE	PROPOSED SIGN CODE	PROPOSED SIGN SIZE	PROPOSED MESSAGE	SIGN PANEL SQ. FT.	POST FOOT	SOLAR POWERED FLASHING BEACON
	START	END							
189			N/A	W3-1	36X36	STOP AHEAD SYMBOL	9.00	15	INSTALL YELLOW FLASHER
190	2.79	2.21	SCENIC HWY	D6-1 PC	24X36	SCENIC HWY	6.00	14	
191	2.79	2.21	NORTH	M3-1	24X12	NORTH	2.00	14	
192	2.79	2.21	PEORIA CO R51	M1-6	24X24	PEORIA CO R51	4.00		
193	2.8	2.2	STOP	R1-1	30X30	STOP	6.25	15	INSTALL RED FLASHER
194	2.8	2.2	ALL WAYS	R1-4	18X6	ALL WAY	0.75		
195			N/A	R1-1	30X30	STOP	6.25	15	INSTALL RED FLASHER
196			N/A	R1-4	18X6	ALL WAY	0.75		
197	2.81	2.19	AIRPORT SYMBOL	I-5	24X24	AIRPORT SYMBOL	4.00	16	
198	2.81	2.19	RT ARROW SYMBOL	M6-1	21X15	RT ARROW SYMBOL	2.20		
199	2.81	2.19	ILLINOIS 116	M1-I100	30X24	ILLINOIS 116	5.00		
200	2.81	2.19	RT ARROW SYMBOL	M6-1	21X15	RT ARROW SYMBOL	2.20		
201	2.82	2.18	HARMAN HWY	D3-1	30X9	HARMAN HIGHWAY 680S	1.88	14	
202	2.82	2.18	KICKAPOO CR ROAD	D3-1	30X9	KICKAPOO CREEK ROAD 4000W	1.88		
203	2.83	2.17	STOP	R1-1	30X30	STOP	6.25	15	INSTALL RED FLASHER
204	2.83	2.17	ALL WAYS	R1-4	18X6	ALL WAY	0.75		
205	2.83	2.17	STOP	R1-1	30X30	STOP	6.25	15	INSTALL RED FLASHER
206	2.83	2.17	ALL WAYS	R1-4	18X6	ALL WAY	0.75		
207	2.83	2.17	<-> SYMBOL	W1-7	48X24	<-> SYMBOL	8.00	14	
208	2.84	2.16	AIRPORT SYMBOL	I-5	24X24	AIRPORT SYMBOL	4.00	16	
209	2.84	2.16	LEFT ARROW SYM	M6-1	21X15	LT ARROW SYMBOL	2.20		
210	2.84	2.16	ILLINOIS 116	M1-I100	30X24	ILLINOIS 116	5.00		
211	2.84	2.16	LEFT ARROW SYM	M6-1	21X15	LT ARROW SYMBOL	2.20		
212	2.84	2.16	STOP	R1-1	30X30	STOP	6.25	15	INSTALL RED FLASHER
213	2.84	2.16	ALL WAYS	R1-4	18X6	ALL WAY	0.75		
214	2.84	2.16	NO CLASS 1-2-3	R5-I102	24X36	NO CLASS 1-2-3 TRUCK ACCESS	6.00	14	
215	2.85	2.15	LOW CLEAR 12'-0"	W12-2	36X36	12'-0"	9.00	15	
216	2.85	2.15	1 MILE AHEAD	W16-3	24X24	1 MILE	4.00		
217	2.85	2.15	STOP	R1-1	30X30	STOP	6.25	15	INSTALL RED FLASHER
218	2.85	2.15	ALL WAYS	R1-4	18X6	ALL WAY	0.75		
219	2.85	2.15	SCENIC HWY	D6-1 PC	24X36	SCENIC HWY	6.00	14	
220	2.86	2.14	CURVE LEFT	W1-2aL	36X36	CURVE LEFT 30	9.00	14	
221	2.86	2.14	SOUTH	M3-3	24X12	SOUTH	2.00	14	
222	2.86	2.14	PEORIA CO R51	M1-6	24X24	PEORIA CO R51	4.00		
223	2.94	2.06	TRUCK X-ING SYM	W11-10	30X30	TRUCK CROSSING SYMBOL	6.25	14	
224			N/A	W3-1	36X36	STOP AHEAD SYMBOL	9.00	15	INSTALL YELLOW FLASHER
225	2.94	2.06	\$200 FINE: TRASH	R15-I100	24X24	PENALTY FOR DUMPING ON PUBLIC HWY	4.00	14	
226			N/A	OM-3R	12X36	OBJECT MARKER	3.00	12	
227	2.96	2.04	SPEED LIMIT 40	R2-1	24X30	SPEED LIMIT 40	5.00	14	
228	2.98	2.02	FALLING ROCK	W8-1 PC	30X30	FALLING ROCK	6.25	14	
229	2.98	2.02	NEXT 1 MILE	W7-3a	24X18	NEXT 1 MILE	3.00		
230			N/A	OM-3R	12X36	OBJECT MARKER	3.00	12	
231	3.01	1.99	R X R	W10-1	36" DIA.	R X R	7.00	14	
232	3.01	1.99	EXEMPT	W10-1a	24X12	EXEMPT	2.00		
233			N/A	OM-3R	12X36	OBJECT MARKER	3.00	12	
234			N/A	OM-3R	12X36	OBJECT MARKER	3.00	12	
235			N/A	OM-3R	12X36	OBJECT MARKER	3.00	12	