

SCHEDULE OF QUANTITIES

SURVEY MARKER COVER ASSEMBLY (Z0070100)

STATION	EACH
55+93.12	1
82+39.70	1
108+30.80	1
108+61.60	1
123+51.40	1
124+97.70	1
161+01.20	1
161+27.80	1
187+28.10	1
213+58.30	1
213+90.60	1
239+86.80	1
266+14.00	1
266+51.00	1
292+29.80	1
292+73.80	1
318+61.10	1
318+27.00	1
TOTAL	18

RUMBLE STRIPS (Z0055300)

SB LANE ONLY - APROX. STA.	EACH
359+50.0 TO 359+75.0	1
366+50.0 TO 366+75.0	1
368+50.0 TO 368+75.0	1
TOTAL =	3

THERMOPLASTIC PAVEMENT MARKINGS LETTERS AND SYMBOLS (78000100)

STATION TO STATION (TYPE)	= X =	SQ FT
STA. RT. 342+16.3 ~ RT. 342+36.3 (1.5 ~ 9.5' RT.)		54.0
STA. RT. 342+23.3 ~ RT. 342+29.3 = R =		3.6
STA. RT. 342+23.3 ~ RT. 342+29.3 = R =		3.6
STA. LT. 348+71.0 ~ LT. 348+91.0 (1.5 ~ 9.5' LT.) = X =		54.0
STA. LT. 348+78.0 ~ LT. 348+84.0 = R =		3.6
STA. LT. 348+78.0 ~ LT. 348+84.0 = R =		3.6
TOTAL		122.4
USE		123.0

PAINT PAVEMENT MARKINGS LINE 4" (78001110)

STA	TO	STA	LENGTH FEET	YELLOW FEET	WHITE FEET
11+18.21		370+47.00	35,928.79	8,978.95	7,185.78
NO PASSING:					
342+00.00		345+60.00	360.00	360.00	
345+47.00		349+07.00	360.00	360.00	
SUB-TOTAL:				9,698.95	71,857.58
TOTAL				81,556.53	
USE				81,557.00	

PAINT PAVEMENT MARKINGS LINE 24" (78001180)

STATION	OFF SET	LT/RT	LENGTH FEET
342+00.3	1' - 11'	RT.	10
342+50.3	1' - 11'	RT.	10
345+34.3	1' - 11'	RT.	10
345+71.0	1' - 11'	LT.	10
348+03.0	1' - 11'	LT.	10
348+53.0	1' - 11'	LT.	10
TOTAL			60

SHORT TERM PAVEMENT MARKINGS (70300100) STA. 11+18.21 TO STA. 370+47.0 = 3593 FT THREE APPLICATIONS = (10,780 FT)

WORK ZONE PAVEMENT MARKING REMOVAL (70301000) STA. 11+18.21 TO STA. 370+47.0 = 1,198 SQ.FT.

TEMPORARY RAMPS (40600990)

LOCATION	STATION	TO	STATION	LENGTH	WIDTH	SQYD
BEGIN JOB	11+18.21		11+23.21	5.00	24	13.33
RR NORTH END	345+44.45		345+49.45	5.00	24	13.33
RR SOUTH END	345+57.85		345+62.85	5.00	24	13.33
END JOB	370+17.00		370+22.00	5.00	24	13.33
TOTAL						53.33
USE						54.00

* TAPER RATE OF 1:40
* THICKNESS = 1.5 INCHES

HMA SURFACE REMOVAL-BUTT JOINT (40600982)

LOCATION	STATION	TO	STATION	LENGTH	WIDTH	SQYD
BEGIN JOB	11+18.21		11+23.21	30.00	24	80.00
RR NORTH END	345+29.50		345+49.45	20.00	29.5	65.56
RR SOUTH END	345+57.85		345+76.05	19.00	29.5	62.28
END JOB	370+17.00		370+22.00	30.00	24	80.00
TOTAL						287.83
USE						288.00

* TAPER RATE OF 1:240
* THICKNESS = 1.5 INCHES