PAVEMENT SCHEDULE

STATION TO STATION	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	HOT-MIX ASPHALT BINDER COURSE	AGGREGATE SHOULDERS, TYPE B	AGGREGATE (PRIME COAT)	AGGREGATE BASE COURSE TYPE A	BITUMINOUS MATERIALS (PRIME COAT)	TEMPORARY RAMPS	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
	TON					GALLON	SQ YD	
215+98.97 TO 216+78.97	16.4	11.5	8.0			15.1	12.2	195.6
216+78.97 TO 222+98.20	127.1	534.7	124.0			116.9		
222+98.20 TO 243+68.60	425.1	1,058.7	414.1			391.0		
243+68.60 TO 272+86.69	599.2	998.6	877.4	10.9	5,465.9	2,999.6		
272+86.69 TO 284+06.84	230.0	592.7	224.5			211.5	12.2	195.6
DONALDSON & LAIR RD.	24.2	24.2	19.5			10.8	24.4	26.7
PROJECT TOTAL	1,422.1	3,220.4	1,667.5	10.9	5,465.9	3,744.9	48.8	417.9
USE	1,423	3,221	1,668	11	5,466	3,745	49	418

SEEDING, CLASS 2 (SPECIAL)

STATION TO STATION	SIDE	AREA	NITROGEN FERTILIZER NUTRIENT •	PHOSPHORUS FERTILIZER NUTRIENT•	POTASSIUM FERTILIZER NUTRIENT•	MULCH METHOD 2•
		ACRE	LBS	LBS	LBS	TONS
241+00 TO 247+60	LT	0.3	20.0	80.0	40.0	0.5
241+00 TO 247+60	RT	0.4	33.6	134.4	67.2	0.8
247+76 TO 256+68	LT	0.7	55.2	220.8	110.4	1.4
247+76 TO 256+68	RT	0.7	54.4	217.6	108.8	1.4
256+84 TO 263+00	LT	0.5	36.0	144.0	72.0	0.9
256+84 TO 263+00	RT	1.0	76.0	304.0	152.0	1.9
263+00 TO 270+70	LT	1.3	107.2	428.8	214.4	2.7
263+00 TO 270+70	RT	0.5	36.8	147.2	73.6	0.9
270+70 TO 274+00	LT	0.2	15.2	60.8	30.4	0.4
270+70 TO 274+00	RT	0.2	12.0	48.0	24.0	0.3
PROJECT TOTAL		5.6	446.4	1,785.6	892.8	11.2
USE		5.6	446.4	1,785.6	892.8	11.2

• INCLUDED IN COST OF SEEDING

PAVEMENT MARKING SCHEDULE

LOCATION	SIDE	PAINT	
		5" SKIP-DASH, YELLOW	5" SOLID, WHITE
		FOOT	
215+98.97 TO 255+00	LT	975.3	3,901.0
215+98.97 TO 255+00	RT	975.3	3,901.0
255+00 TO 284+06.84	LT	726.6	2,906.5
255+00 TO 284+06.84	RT	726.7	2,906.6
PROJECT TOTAL		3,403.8	13,615.1
USE		17,019	

INLET AND PIPE PROTECTION

STATION	OFFSET	SIDE	EACH
	FOOT		
247+50	33.0	RT	1
248+00	28.0	LT	1
254+50	46.0	LT	1
260+15	44.0	LT	1
268+50	42.0	LT	1
272+33	29.0	LT	1
273+21	29.0	LT	1
TOTAL			7

TEMPORARY DITCH CHECKS

STATION TO STATION	SIDE	EACH	LENGTH
			FOOT
244+30.0 TO 250+50.0	LT	6	69
246+43.3 TO 248+75.0	RT	4	46
252+25.0 TO 254+55.0	LT	6	69
251+93.7 TO 254+55.0	RT	10	115
255+28.2 TO 256+55.0	LT	4	46
254+65.0 TO 255+83.7	RT	7	80.5
257+68.2 TO 259+32.7	LT	3	34.5
257+34.9 TO 259+21.5	RT	3	34.5
260+09.9 TO 261+70.5	LT	5	57.5
260+09.9 TO 261+45.3	RT	4	46
263+55.7 TO 264+30.0	LT	2	23
262+10.5 TO 262+75.7	RT	2	23
267+07.1 TO 268+55.0	LT	4	46
265+86.0 TO 268+15.0	RT	5	57.5
268+98.3 TO 269+94.9	LT	3	34.5
268+67.3 TO 269+81.9	RT	3	34.5
270+43.2 TO 272+23.1	LT	5	57.5
270+39.2 TO 273+11.5	RT	5	57.5
TOTAL			931.5
USE			932

ESTIMATED QUANTITIES

ITEMS	UNIT	TOTAL
THE FOLLOWING ITEMS INCLUDE ESITMATED QUANTITIES FOR HANDLING FIELD TILES WITHIN THE PROJECT LIMITS (SEE SPECIAL PROVISIONS)		
STORM SEWER (SPECIAL) 6"	FOOT	200
STORM SEWER (SPECIAL) 8"	FOOT	200
STORM SEWER (SPECIAL) 12"	FOOT	200

PERIMETER EROSION BARRIER

STATION TO STATION	SIDE	FOOT
241+00 TO 248+00	LT	685.0
241+00 TO 248+00	RT	700.0
248+00 TO 258+00	LT	1003.0
248+00 TO 258+00	RT	1004.0
258+00 TO 268+00	LT	1140.0
258+00 TO 268+00	RT	1086.0
268+00 TO 274+00	LT	616.0
268+00 TO 274+00	RT	574.0
TOTAL		6808.0
USE		6808