

SUMMARY OF QUANTITIES			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100500	TREE REMOVAL ACRES	ACRE	1.75
20200100	EARTH EXCAVATION	CU YD	2,416
20400800	FURNISHED EXCAVATION	CU YD	5,158
20900110	POROUS GRANULAR BACKFILL	CU YD	360
20900410	SAND BACKFILL	CU YD	345
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	717
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	882
25000305	SEEDING, CLASS 3A	ACRE	1.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	158
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	158
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	158
25000700	AGRICULTURAL GROUND LIMESTONE	TON	4
25100115	MULCH, METHOD 2	ACRE	1.25
25100630	EROSION CONTROL BLANKET	SQ YD	3,197
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	25
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	350
28000305	TEMPORARY DITCH CHECKS	FOOT	60
28000400	PERIMETER EROSION BARRIER	FOOT	526
28001000	AGGREGATE (EROSION CONTROL)	TON	53
28100207	STONE RIPRAP, CLASS A4	TON	345
28200200	FILTER FABRIC	SQ YD	461
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	249
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	115
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	60
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	33
48101200	AGGREGATE SHOULDERS, TYPE B	TON	62
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50104000	BRIDGE RAIL REMOVAL	FOOT	88
50200100	STRUCTURE EXCAVATION	CU YD	565
50200300	COFFERDAM EXCAVATION	CU YD	300
50200500	COFFERDAMS	EACH	1
50300225	CONCRETE STRUCTURES	CU YD	493.1
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1,232

SUMMARY OF QUANTITIES			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
50800105	REINFORCEMENT BARS	POUND	71,440
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	490
50900205	STEEL RAILING, TYPE S1	FOOT	88
51500100	NAME PLATES	EACH	1
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	137
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	264
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	224
60107600	PIPE UNDERDRAINS 4"	FOOT	300
63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	50
63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4
63200310	GUARD RAIL REMOVAL	FOOT	180.0
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	104.5
63302000	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2
66400535	CHAIN LINK FENCE, 6' ATTACHED TO STRUCTURE	FOOT	370
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	6.25
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	17
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	282
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1
LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1
XX007958	DIVERSION STRUCTURE	EACH	1
X0301280	PLUG EXISTING DRAINS	EACH	1
X0323265	REMOVE EXISTING RIPRAP	SQ YD	40
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0018905	DRILL AND GROUT BARS	EACH	56
XX008370	PVC WATERSTOP, 6"	FOOT	521
XX008371	TEMPORARY DRAWDOWN PIPE	EACH	1
XX008372	SLUICE GATE	EACH	1

△ SPECIALTY ITEMS

CONSTRUCTION TYPE CODE: Y009

FILE NAME =  
...Sheets\NemanvilleTr\_S001.dgn

USER NAME = Kristin Timmons	DESIGNED - KLT/JJF	REVISED -
PLOT SCALE = 50,0000' / IN.	DRAWN - GLD	REVISED -
PLOT DATE = 3/4/2010	CHECKED - KLT/JJF	REVISED -
	DATE - 3/2/2010	REVISED -

**NIEMANVILLE TRAIL  
MONTGOMERY COUNTY, ILLINOIS**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 32 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8243	09-00134-00-DR	MONTGOMERY	32	3
CONTRACT NO. 99537				
FED. ROAD DIST. NO. 6 [ILLINOIS] FED. AID PROJECT				