

SIDEWALK REMOVAL SCHEDULE

LOCATION	SIDEWALK REMOVAL (SQ FT)
STATE STREET	
STA. 98+91.50 - 53.72' LT TO STA. 99+05.13 - 42.46' LT	81.33
STA. 99+06.57 - 39.18' RT TO STA. 99+17.99 - 26.95' RT	74.52
STA. 102+39.56 - 23.76' RT TO STA. 102+48.68 - 23.85' RT	51.05
STA. 102+86.68 - 25.72' RT TO STA. 102+94.40 - 25.72' RT	51.79
STA. 105+92.20 - 23.62' RT TO STA. 106+05.00 - 29.55' RT	87.26
STA. 106+51.40 - 31.51' RT TO STA. 106+67.16 - 24.08' RT	147.97
STA. 109+52.14 - 24.22' RT TO STA. 109+67.61 - 30.21' RT	136.31
STA. 110+11.13 - 29.24' RT TO STA. 110+23.05 - 23.68' RT	88.01
STA. 113+13.55 - 24.45' RT TO STA. 113+27.80 - 31.65' RT	128.67
STA. 113+70.18 - 28.30' RT TO STA. 113+88.30 - 23.83' RT	139.46
STA. 116+77.63 - 23.62' RT TO STA. 116+87.86 - 28.76' RT	72.37
STA. 117+29.03 - 32.86' RT TO STA. 117+40.97 - 24.58' RT	139.53
STA. 120+42.08 - 23.71' RT TO STA. 120+56.36 - 23.84' RT	76.79
STA. 121+04.60 - 24.05' RT TO STA. 121+15.05 - 24.02' RT	69.30
STA. 124+12.45 - 23.93' RT TO STA. 124+27.55 - 31.68' RT	110.55
STA. 124+71.52 - 29.21' RT TO STA. 124+83.12 - 23.06' RT	88.88
STA. 127+72.80 - 22.73' RT TO STA. 127+87.88 - 27.71' RT	110.37
STA. 128+29.37 - 27.79' RT TO STA. 128+38.94 - 27.76' RT	91.18
STA. 134+92.99 - 29.92' RT TO STA. 135+07.29 - 55.58' RT	155.48
STA. 135+51.52 - 35.30' RT TO STA. 135+64.18 - 30.02' RT	114.26
STA. 142+13.38 - 32.69' RT TO STA. 142+28.46 - 33.13' RT	93.86
STA. 142+70.24 - 40.77' RT TO STA. 142+79.73 - 27.07' RT	108.72
STA. 148+19.00 - 33.26' RT TO STA. 148+27.06 - 32.96' RT	40.99
STA. 148+70.29 - 39.08' RT TO STA. 148+78.97 - 31.19' RT	74.86
STA. 154+79.62 - 30.91' RT TO STA. 154+89.93 - 30.91' RT	45.92
STA. 155+27.22 - 30.89' RT TO STA. 155+38.94 - 30.89' RT	55.23
TOTAL	2435

PAVING SCHEDULE

LOCATION	PAVEMENT AREA (SQ YD)	BIT MATL PR CT (GALLON)	AGGREGATE (PRIME COAT) (TON)	LEVELING BINDER (MACHINE METHOD), N70, 1 1/2" (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1 1/2" (TON)
STATE STREET					
STA. 98+98.15 TO STA. 155+34.54	21790.0	1525.3	43.6	1830.4	1830.4
TOTAL		1525	44	1830	1830

HOT-MIX ASPHALT SURFACE REMOVAL SCHEDULE

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL (SQ YD)
STATE STREET	
STA. 98+98.15 TO STA. 155+34.54	21820.0
TOTAL	21820

STORM SEWER SCHEDULE

STRUCTURE NO.	LOCATION	STORM SEWERS, CLASS A			STORM SEWERS, CLASS B, TYPE 1 (FOOT)	TRENCH BACKFILL (CU YD)
		TYPE 1 (FOOT)		TYPE 2 (FOOT)		
		12"	15"	15"		
	STATE STREET					
S-1 TO S-2	STA. 100+94.95 - 44.55' LT TO STA. 101+16.22 - 72.29' LT			32		20
S-3 TO S-4	STA. 102+26.75 - 17.80' LT TO STA. 102+27.02 - 18.14' RT		33			5
S-5 TO M-1	STA. 120+55.87 - 28.00' RT TO STA. 120+78.80 - 28.00' RT	20				2
S-6 TO M-1	STA. 121+02.71 - 27.00' RT TO STA. 120+78.80 - 28.00' RT	21				2
S-7 TO M-2	STA. 148+09.54 - 24.11' RT TO STA. 148+49.50 - 25.66' RT				37	7
TOTAL		41	33	32	37	36

CURB AND GUTTER REMOVAL SCHEDULE

LOCATION	REMOVAL	
	CONCRETE CURB, TYPE B (FOOT)	CONCRETE CURB AND GUTTER, TYPE B-6.12 (FOOT)
STATE STREET		
STA. 102+24.76 - 16.54' LT TO STA. 102+28.76 - 16.48' LT	4	
STA. 102+93.16 - 18.79' LT TO STA. 103+02.91 - 16.21' LT	10	
STA. 103+02.91 - 15.65' LT TO STA. 103+20.62 - 15.64' LT		18
STA. 102+25.01 - 16.15' RT TO STA. 102+29.01 - 16.17' RT	4	
STA. 102+39.76 - 16.32' RT TO STA. 102+48.68 - 23.85' RT	13	
STA. 102+86.02 - 25.72' RT TO STA. 102+94.40 - 16.19' RT		14
STA. 120+57.85 - 25.59' RT TO STA. 120+58.65 - 29.78' RT		4
STA. 120+99.36 - 29.34' RT TO STA. 121+00.58 - 25.08' RT		4
STA. 128+66.26 - 15.26' RT TO STA. 128+71.72 - 15.21' RT		5
STA. 132+19.30 - 15.28' RT TO STA. 132+69.55 - 15.31' RT		50
STA. 132+84.47 - 15.39' RT TO STA. 133+28.73 - 15.61' RT		44
STA. 134+40.40 - 18.90' RT TO STA. 135+08.06 - 37.96' RT		79
STA. 135+48.25 - 34.53' RT TO STA. 135+57.80 - 22.36' RT		17
STA. 138+83.80 - 23.06' RT TO STA. 138+88.95 - 23.05' RT		5
STA. 141+09.14 - 23.02' RT TO STA. 141+29.21 - 23.00' RT		20
STA. 142+92.78 - 22.87' RT TO STA. 143+09.43 - 22.88' RT		17
STA. 144+63.64 - 22.87' RT TO STA. 144+78.62 - 22.88' RT		15
STA. 146+33.67 - 22.86' RT TO STA. 146+58.75 - 22.91' RT		25
STA. 146+78.58 - 22.66' RT TO STA. 146+93.77 - 22.83' RT		15
STA. 148+11.54 - 22.82' RT TO STA. 148+28.55 - 34.10' RT		22
STA. 148+90.97 - 22.80' RT TO STA. 148+96.16 - 22.81' RT		5
STA. 151+51.22 - 22.81' RT TO STA. 151+61.50 - 22.81' RT		10
STA. 151+96.28 - 22.79' RT TO STA. 152+06.64 - 22.79' RT		10
TOTAL	31	381

STORM SEWER REMOVAL

LOCATION	STORM SEWER REMOVAL (FOOT)	
	8" VCP	15" RCCP
STATE STREET		
STA. 100+94.95 - 44.55' LT TO STA. 101+16.22 - 72.29' LT		32
STA. 102+26.75 - 17.80' LT TO STA. 102+27.02 - 18.14' RT		33
STA. 120+55.87 - 28.00' RT TO STA. 120+78.80 - 28.00' RT	20	
STA. 121+02.71 - 27.00' RT TO STA. 120+78.80 - 28.00' RT	21	
STA. 148+09.54 - 24.11' RT TO STA. 148+49.50 - 25.66' RT		37
TOTAL	78	65