



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 25, 2010

SUBJECT: FAU 9307 (Kunz Street)  
Project M-5011(313)  
Section 06-00042-02-PV (Columbia)  
Monroe County  
Contract No. 97444  
Item 309  
June 11, 2010 Letting  
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

**Proposal – Index to Special Provisions, pages 1 & 2 of the special provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott Stitt  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "AE" monogram.

By: Ted B. Walschleger  
Engineer of Project Development  
and Implementation

**SPECIAL PROVISIONS  
FAU ROUTE 9307 (KUNZ STREET)  
SECTION 06-00042-02-PV  
COLUMBIA, ILLINOIS**

**INDEX TO SPECIAL PROVISIONS**

DESCRIPTION OF WORK.....	1
EMPLOYMENT SOLICITATION.....	1
<del>EXAMINATION OF THE SITE.....</del>	<del>1-2</del>
SHOP DRAWINGS.....	2
CONSTRUCTION STAKING.....	2-4
SAFETY AND HEALTH.....	4
SAFETY AND PROTECTION.....	4-5
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT.....	5
CONSTRUCTION CONTRACTS.....	6
SEQUENCE OF CONSTRUCTION OPERATIONS.....	6-7
TRAFFIC CONTROL PLAN.....	7-8
PUBLIC NOTICE.....	8
EARTH EXCAVATION.....	9
TRENCH BACKFILL.....	9
SEEDING, CLASS 1B.....	10
INCIDENTAL HOT-MIX ASPHALT SURFACING.....	10
PORTLAND CEMENT CONCRETE PAVEMENT, THICKNESS SPECIFIED.....	10-11
EXPANSION JOINTS.....	11-12
DETECTABLE WARNINGS.....	12-13
STEEL RAILING.....	13-14
STORM SEWER, CLASS A.....	14
CONTROLLED LOW-STRENGTH MATERIAL.....	14
ROOF DRAIN ADJUSTMENT.....	14-15
MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID.....	15
TYPE 3 AND 3V FRAME AND GRATE.....	15-16
CONCRETE CURB (SPECIAL).....	16
CURB & GUTTER TRANSITIONS.....	16
TRAFFIC CONTROL AND PROTECTION.....	16-17
CONTRACTOR ACCESS.....	17
TEMPORARY PAVEMENT MARKING.....	17-18
SHREDDED BARK MULCH.....	18
STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE.....	18
STORM SEWER (WATER MAIN REQUIREMENTS).....	19
LANDSCAPING GRAVEL.....	19
FILLING EXISTING VAULT.....	19
INLETS, TYPE SPECIFIED, TYPE 3V FRAME AND GRATE.....	20
CONCRETE STEPS.....	20
PAINT CURB.....	20-21
STATUS OF UTILITIES TO BE ADJUSTED.....	22
PAYROLLS AND PROCEDURES.....	23-
MONTHLY LABOR SUMMARY AND ACTIVITY REPORTING SYSTEM.....	24-25

Revised 5-25-10

**SPECIAL PROVISIONS  
FAU ROUTE 9307 (KUNZ STREET)  
SECTION 06-00042-02-PV  
COLUMBIA, ILLINOIS**

The following special provisions supplement the "Standard Specifications for Road and Bridge Construction," prepared by the Illinois Department of Transportation and adopted January 1, 2007, the latest edition of the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways" in effect on the date of the invitation for bids, the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids and the "Supplemental Specifications and Recurring Special Provisions" indicated on the check sheet included herein and the "Standard Specifications for Water and Sewer Construction in Illinois", Adopted July 2009, which apply to and govern the construction of KUNZ STREET, SECTION 06-00042-02-PV, Columbia, Illinois, and in case of conflict with any part or parts of said specifications, these special provisions shall take precedence and shall govern.

**DESCRIPTION OF WORK**

The proposed reconstruction project is located on Kunz Street from Legion Street to Main Street in Columbia, Illinois. The project length is 1,206.07 feet (0.228 miles).

The work on this project consists of removals; earthwork, sub-base granular material, non-reinforced Portland cement concrete pavement, concrete curb & gutter, driveway pavement, sidewalk, storm sewers and paint pavement markings and all incidental and collateral work necessary to complete the work in the above-described Section according to the plans, specifications and special provisions.

**EMPLOYMENT SOLICITATION**

The Contractors shall notify the Department's Agency Ethics Officer if they solicit or intend to solicit for employment any of the Illinois Department of Transportation's employees during any part of the procurement process or during the term of the contract. The Department's Agency Ethics Officer is the Chief Counsel who can be contacted at (217) 782-0691.

~~**EXAMINATION OF THE SITE**~~ Deleted

~~The bidder shall, before submitting a bid on any contract item, carefully examine the provisions of the contract documents for bidding and all contract documents referenced therein that comprise the contract as defined in Article 101.09 of the "Standard Specifications for Road and Bridge Construction." The bidder shall inspect in detail the site of the proposed work, investigate and become familiar with all the local conditions affecting the contract and the detailed requirements of construction.~~

~~Submission of a bid shall be a conclusive assurance and warranty the bidder has made these examinations and the bidder understands all requirements for the performance of the work. If the bid is accepted, the bidder will be responsible for all errors in the proposal resulting from a failure or neglect to comply with these instructions. The City of Columbia and their officers, agents and~~

~~employees will not be responsible for any costs, expenses, losses, or change in anticipated profits resulting from the failure or neglect of the bidder to make these examinations. The bidder shall take no advantage of any error or omission in the proposal and advertised contract.~~

### **SHOP DRAWINGS**

The Contractor shall submit shop drawings of the following items according to Article 1042.03(b) of the "Standard Specifications for Road and Bridge Construction":

- Concrete Steps
- Precast Concrete Inlets
- Precast Concrete Manholes
- Type 1 Frame and Lid for Sanitary Sewer Manhole Adjustments
- Type 3 Frame and Grate
- Detectable Warnings
- Stair Side Railing
- Filling Existing Vault (foundation and wall detail)
- Landscape Gravel (sample)

Submit shop drawings for review and approval to:

Mr. Ron Williams, PE, City Engineer  
City of Columbia  
208 South Rapp Street  
Columbia, Illinois 62236

A maximum of two reviews by the Engineer will be provided for each shop drawing submittal. If any additional reviews are required, the Contractor shall pay the Engineer for all costs incurred at an hourly rate of \$150.

### **CONSTRUCTION STAKING**

This item shall consist of construction staking according to Article 105.09 of the "Standard Specifications for Road and Bridge Construction", except as modified herein.

The Local Agency will provide adequate reference points to the baseline of survey and bench marks as shown in the plans and listed herein. Any additional control points set by the Local Agency will be identified in the field to the Contractor and all field notes will be kept in the office of the Resident Engineer.

The Contractor shall provide labor, equipment and material to set all additional stakes for this project, which are needed to establish offset stakes, reference points, and any other horizontal or vertical controls, including supplementary bench marks, necessary to secure a correct layout for the roadway portion of the work.

The Contractor shall be responsible for having the finished work conform to the lines, grades,