

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	8
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	

\* FAU 9481, FAS 2887 (IL 37)  
 \*\* (12,12X),RS-3;12B-1,12B1-1  
 \*\*\* FRANKLIN AND WILLIAMSON

# SUMMARY OF QUANTITIES

<b>COUNTY:</b>	FRANKLIN	ACRS	WILLIAMSON
<b>LOCATION:</b>	URBAN		RURAL
<b>ROUTE:</b>	FAU 9481 (IL 37) STA 79+75 TO 94+19.2; STA 366+03.61 TO 374+30	FAS 2887 (IL 37) STA 374+30 TO 457+12 80% FED/ 20% STATE-STP	FAS 2887 (IL 37) STA 457+12 TO 577+41 80% FED/ 20% STATE-STP
<b>FUNDING:</b>	80% FED/ 20% STATE-STP		
<b>WORK TYPE:</b>	ROADWAY	BOX CULVERT SN 028-2017	BRIDGE SN 028-0078
	I000-2A	X028-2A	X071-2A
			ROADWAY
			I000-2A

CODE NUMBER	ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE:		TOTAL PLAN QUANTITY				
			I000-2A	X028-2A					
54010202	PRECAST CONCRETE BOX CULVERT 2' X 2'	FOOT			99.0				22.0
54010303	PRECAST CONCRETE BOX CULVERT 3' X 3'	FOOT			24.0				442.0
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT			442.0				35.0
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT			35.0				45.0
54010404	PRECAST CONCRETE BOX CULVERT 4' X 4'	FOOT			74.0				237.0
54010502	PRECAST CONCRETE BOX CULVERT 5' X 2'	FOOT			237.0				664.0
54010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT			664.0				60.0
54010604	PRECAST CONCRETE BOX CULVERT 6' X 4'	FOOT			60.0				23.0
54011004	PRECAST CONCRETE BOX CULVERT 10' X 4'	FOOT			23.0				22.0
54200211	PIPE CULVERTS, CLASS D, TYPE 1 6"	FOOT			22.0				439.0
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT			969.0				29.0
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT			632.0				603.0
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT			265.0				265.0
54200232	PIPE CULVERTS, CLASS D, TYPE 1 27"	FOOT			29.0				64.0
54200235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT			64.0				97.0
54200241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT			97.0				601.0
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT			1,612.0				22.0
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT			720.0	32.0			197.0
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT			371.0	12.0			162.0
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT			141.0	94.0			47.0
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT			30.0				14.0
542A5477	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT			118.0				125.0
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT			125.0				480.0
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT			480.0				163.0
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT			163.0				62.0
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT			62.0				24.0
54213450	END SECTIONS 15"	EACH			50.0				2.0
54213453	END SECTIONS 18"	EACH			34.0				14.0
54213459	END SECTIONS 24"	EACH			14.0				2.0
54213462	END SECTIONS 27"	EACH			2.0				4.0
54213465	END SECTIONS 30"	EACH			6.0				4.0
54213471	END SECTIONS 36"	EACH			4.0				38.0
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH			106.0				2.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH			32.0	2.0			12.0
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH			24.0	4.0			2.0
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH			6.0	4.0			2.0
54214713	FLARED END SECTIONS - ELLIPTICAL, 18"	EACH			4.0				6.0
54214719	FLARED END SECTIONS - ELLIPTICAL, 24"	EACH			6.0				6.0
54214725	FLARED END SECTIONS - ELLIPTICAL, 30"	EACH			6.0				6.0

PRECAST REINFORCED CONCRETE EQUIVALENT ROUND-SIZE

SHEET 4 OF 6

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<h2>SUMMARY OF QUANTITIES</h2> <p>SCALE: VERT. NO SCALE                  HORIZ. NO SCALE</p> <p>DRAWN BY CNH                  CHECKED BY</p>

PLOT DATE = 3/2/2010  
 FILE NAME = c:\pwworking\SWI\DOT\VEE\SBF\dms13559\984823r.dgn  
 PLOT SCALE = 0.000000  
 USER NAME = wmmind