

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* FAU 9481, FAS 2887 (IL 37)
 ** (12,12X),RS-3;12B-1,12B1-1
 *** FRANKLIN AND WILLIAMSON

TREE REMOVAL

LOCATION STATION TO STATION		OFFSET FROM CENTERLINE FEET	TREE REMOVAL 6 TO 15 UNITS DIAMETER UNIT	TREE REMOVAL OVER 15 UNITS DIAMETER UNIT	TREE REMOVAL ACRES	REMARKS
RT STA	482+50	34			29	
RT STA	482+86	32			17	
RT STA	482+97	31			29	
RT STA	483+40	38			28	
RT STA	484+52	48	26			15" AND 11" TREES
RT STA	484+59	47	7			
RT STA	484+63	50			22	
RT STA	484+66	49	8			
RT STA	485+40	46	8			
RT STA	488+20	53	9			
RT STA	489+45	49			26	
RT STA	490+20	50				LESS THAN 6"
RT STA	490+60	50			32	
RT STA	492+96	48	15			
RT STA	499+29	40	12			TWO 6" TREES
RT STA	500+38	38	6			
LT STA	500+15 TO 501+14	36' TO 45'			0.02	RECTANGULAR SHAPED AREA (SEE PLANS)
LT STA	504+60	47	15			
LT STA	505+41	37	9			
LT STA	505+64	37	10			
LT STA	506+31	37	12			
RT STA	512+91	43	30			THREE 10" TREES
RT STA	515+22	50			22	
RT STA	515+60	50			30	
LT STA	518+15	45			32	
LT STA	519+37 TO 521+64	25' TO 45'			0.09	RECTANGULAR SHAPED AREA (SEE PLANS)
LT STA	522+32 TO 524+76	24' TO 53'			0.17	RECTANGULAR SHAPED AREA (SEE PLANS)
LT STA	525+84	34			28	10 FT REMAINING OF CUT TREE
LT STA	527+60	50			44	4 LARGE TREES TOGETHER
LT STA	527+74	50	27		34	12", 15", 16", AND 18" TREES
RT STA	528+87	33			29	
RT STA	529+07	33			18	
RT STA	529+25	33			25	
RT STA	529+85	33			43	21" AND 22" TREES
RT STA	530+30	33' AND 45'	23		16	11" TREE AT 45' ; 12" AND 16" TREES AT 33'
RT STA	530+41	33			25	
LT STA	530+46	77			19	
RT STA	530+64	33' AND 70'			24	TREE AT 70' IS < 6"
RT STA	530+71	67				TREE < 6"
RT STA	530+84	33			30	
RT STA	530+95	67				TREE < 6"
RT STA	531+28	33			41	21" AND 20" TREES
LT STA	531+47	54			30	
RT STA	532+98	33			44	
RT STA	533+49	45			38	
LT STA	533+58	41	12			TWO 6" TREES
LT STA	534+12	61			17	
LT STA	534+85	59	14			
RT STA	535+02	54			16	
RT STA	535+24	54	8			
RT STA	535+46	54	12			
RT STA	535+69	54	20			8" AND 12" TREES
RT STA	535+92	54	16			TWO 8" TREES
RT STA	536+09	52	10			
RT STA	536+18	52	13			6" AND 7" TREES
RT STA	536+27	52			23	
RT STA	536+29	52				TREE < 6"
RT STA	536+43	52				TREE < 6"
RT STA	536+57	52				10" STUMP AND < 6" TREE
LT STA	536+65	28				TREE < 6"
RT STA	536+68	52	11			
LT STA	536+81	51				TREE < 6"
LT STA	536+97	65	12			
LT STA	537+15	57	10			
RT STA	537+25	52	8			
RT STA	537+47	63	15			7" AND 8" TREES
LT STA	537+55	55				TREE < 6"
RT STA	537+57	59				7" STUMP
LT STA	547+93	48			22	
LT STA	548+08	40			22	
LT STA	548+16	54	12			
LT STA	548+32	60				24" STUMP
LT STA	548+65	60				9" STUMP

SHEET 3 OF 4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY