

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* FAU 9481, FAS 2887 (IL 37)
 ** (12.12X),RS-3;12B-1,12B1-1
 *** FRANKLIN AND WILLIAMSON

ENTRANCES

**SEE NOTE

LOCATION STATION TO STATION	EXISTING ENTRANCE		PROPOSED ENTRANCE			BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE BASE COURSE, TYPE B		AGGREGATE SURFACE COURSE, TYPE A TON	AGGREGATE FOR DRIVEWAY MAINTENANCE TON	INCIDENTAL HMA SURFACING TON	PCC DRIVEWAY PAVEMENT		PCC PAVEMENT 8" SQ YD	PAVEMENT FABRIC SQ YD	PROTECTIVE COAT (42001300) SQ YD	REMARKS
	TYPE	SURFACE	WIDTH FT	RADIUS FT	LENGTH* FT		4" SQ YD	8" SQ YD				6" SQ YD	7" SQ YD				
FRANKLIN COUNTY																	
FAU 9481 (IL 37)																	
RT STA 80+06	C. E. R.	BITUMINOUS	25	15	4	5											3P DETAIL
RT STA 81+02	C. E. R.	BITUMINOUS	23	30/10	4	4											3P DETAIL
LT STA 81+08	C. E. L.	BITUMINOUS	30		23	20	62										
RT STA 81+43	C. E. R.	BITUMINOUS	20	10	4	4											3P DETAIL
LT STA 82+39	P. E. L.	ROCK	20	25	26			16	2								
RT STA 82+48	C. E. R.	BITUMINOUS	80	10/35	4	12											3P DETAIL
LT STA 83+56	P. E. L.	ROCK	20	25/15	25			14	2								
RT STA 86+61	C. E. R.	ROCK	20	35	43			35	2								
LT STA 90+99	F. E. L.	DIRT	22	15	50												
LT STA 91+75	P. E. L.	ROCK	12	25/15	41			19	1								
TOTAL FROM PAVEMENT SCHEDULE																182	
LOCATION TOTAL																182	
FAS 2887 (IL 37)																	
LT STA 376+75		PCC	35	50	55			110					258				K&E Tech.
RT STA 377+39	P. E. R.	ROCK	12	25/15	33			13	1								
LT STA 377+81	C. E. L.	PCC	35	30/20	55			60					172			172	AGGREGATE TO BE PLACED BEHIND PCC
LT STA 378+72	C. E. L.	ROCK	30	20/15	55			85	3								QUANTITY INCLUDES PARKING LOT AREA
RT STA 378+95	P. E. R.	ROCK	23	35/20	35			26	3								LENGTH MEASURED ALONG SKEW
LT STA 379+23	C. E. L.	ROCK	22	15	55			42	2								QUANTITY INCLUDES PARKING LOT AREA
LT STA 380+88	C. E. L.	ROCK	35	25/15	59	213		97	4								QUANTITY INCLUDES PARKING LOT AREA
LT STA 381+76	C. E. L.	ROCK	35	15/25	59			98	4								QUANTITY INCLUDES PARKING LOT AREA
LT STA 382+50		ROCK			67												WESTERN STORE PARKING LOT
LT STA 383+26	C. E. L.	ROCK	35	35	40			51	4								
LT STA 384+88	C. E. L.	ROCK	20	30	38			28	2								
RT STA 386+04	P. E. R.	ROCK	18	15	31			17	2								
LT STA 386+61	P. E. L.	ROCK	13	20	40			17	1								
RT STA 386+92	P. E. R.	ROCK	12	20	26			10	1								
RT STA 388+78	P. E. R.	ROCK	20	15	15			6	2								
LT STA 389+69	C. E. L.	ROCK	26	25	35			29	3								
RT STA 390+30 (SPOWART ROAD)	S. R. R.	OIL/CHIP	16	45	55	44	136				23						SEE PLAN DETAIL
LT STA 390+44	C. E. L.	ROCK	35	50	32			68	4								
RT STA 392+13	P. E. R.	BITUMINOUS	13	15	30	10	33				7						
LT STA 392+14	C. E. L.	ROCK	35	50	32			68	4								
LT STA 393+48	P. E. L.	BITUMINOUS	13	15	34	13	39				4						
RT STA 393+59 (CALSBURG ROAD)	S. R. R.	OIL/CHIP	13	45	49	33	105				18						SEE SIDEROAD DETAIL
RT STA 394+44	P. E. R.	PCC	12	15	37							41					41
LT STA 394+86	P. E. L.	BITUMINOUS	13	15	36	13	41				5						
RT STA 395+40	P. E. R.	PCC	12	15	36							39					39
RT STA 396+42	P. E. R.	ROCK	12	15	39												
LT STA 396+59	P. E. L.	BITUMINOUS	12	15	52	19	59				7						
LT STA 397+00	P. E. L.	BITUMINOUS	12	15	42	15	46				5						
RT STA 397+02	P. E. R.	ROCK	12	15	36												
LT STA 399+68	P. E. L.	BITUMINOUS	12	15	31	10	31				3						
LT STA 400+28	P. E. L.	ROCK	12	15	38						14						
RT STA 400+49 (TIPPS ROAD)	S. R. R.	OIL/CHIP	16	45/40	45	34	106										SEE SIDEROAD DETAIL
RT STA 401+95	P. E. R.	ROCK	13	20/10	40												LENGTH MEASURED ALONG SKEW
LT STA 403+70 (WOODY ROAD)	S. R. L.	OIL/CHIP	21	45/40	44	41	127										SEE PLAN DETAIL
RT STA 403+70	P. E. R.	ROCK	12	15	31												
LT STA 406+53	F. E. L.	DIRT	22	15	34												
RT STA 407+15 (COUNTRY CLUB ROAD)	S. R. R.	BITUMINOUS	30	80//50/300	72												SEE PAVEMENT SCHEDULE
LT STA 407+44	C. E. L.	ROCK	12	20/15	29												
LT STA 410+37	P. E. L.	ROCK	12	15	32												

* LENGTHS ARE MEASURED FROM THE EDGE OF PAVEMENT

**THE PROJECT TOTAL QUANTITY OF "AGGREGATE FOR DRIVEWAY MAINTENANCE" AS SCHEDULED, MAY NOT BE REQUIRED AS NOTED, AND CAN BE PLACED AT OTHER MAINTENANCE LOCATIONS AS DIRECTED BY THE ENGINEER.

SHEET 1 OF 4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY