

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	31
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* FAU 9481, FAS 2887 (IL 37)
 ** (12,12X),RS-3;12B-1,12B1-1
 *** FRANKLIN AND WILLIAMSON

INLETS

LOCATION STATION TO STATION	FLUSH INLET BOX FOR MED. STD 542546 SPECIAL	INLET BOX SPECIAL	INLETS, TYPE A, TYPE 8 GRATE	INLETS TYPE B, TYPE 8 GRATE	FRAME AND LIDS, TYPE 1, OPEN LID	MANHOLE SPECIAL TYPE 1	CONCRETE COLLAR	REMOVING INLETS	REMARKS
	EACH	EACH	EACH	EACH	EACH	EACH	CU YD	EACH	
FRANKLIN COUNTY									
FAS 2887 (IL 37)									
LT STA 377+81	1								SEE INLET BOX DETAILS
LT STA 378+99					1				
LT STA 381+33	1							1	SEE INLET BOX DETAILS
LT STA 382+50	1								SEE INLET BOX DETAILS
LT STA 389+98	1								SEE INLET BOX DETAILS
LT STA 391+00	1								SEE INLET BOX DETAILS
LT STA 396+80		1							SEE INLET BOX DETAILS
RT STA 396+57	1							1	SEE INLET BOX DETAILS
RT STA 399+98									
LT STA 411+15			1				0.58		
LT STA 412+91			1				0.58		
LOCATION TOTAL	6	1	2	0	1	1	1.16	1	
TOTAL FROM BOX CULVERT SCHEDULE							3.02		
FRANKLIN COUNTY PROJECT TOTALS	6	1	2	0	1	1	4.2	1	
WILLIAMSON COUNTY									
FAS 2887 (IL 37)									
RT STA 516+00				1			0.64		
RT STA 549+37				1			0.64		
LOCATION TOTAL	0	0	0	2	0	0	1.28	0	
TOTAL FROM BOX CULVERT SCHEDULE							4.88		
WILLIAMSON COUNTY PROJECT TOTALS	0	0	0	2	0	0	6.2	0	
PROJECT TOTALS	6	1	2	2	1	1	10.4	1	

TRENCH BACKFILL

LOCATION STATION TO STATION	TRENCH BACKFILL	POROUS GRANULAR EMBANKMENT	REMARKS
	CU YD	CU YD	
FRANKLIN COUNTY			
FAU 9481 (IL 37)			
STA 91+00		497	SN 028-2017
LOCATION TOTAL	0	497	
FAS 2887 (IL 37)			
RT STA 390+30	9		SPOWART RD
RT STA 393+59	9		CALSBURG RD
RT STA 400+49	13		TIPPS RD
LT STA 403+70	4		WOODY RD
LT STA 457+11	5		COUNTY LINE RD
LOCATION TOTAL	40	0	
FRANKLIN COUNTY TOTALS	40	497	
WILLIAMSON COUNTY			
FAS 2887 (IL 37)			
RT STA 475+14	4		FOX CROFT RD
LT STA 536+43	6		VILLA WAY RD
LT STA 551+76	6		UNION RD
STA 569+00		122	
LOCATION TOTAL	16	122	
WILLIAMSON COUNTY TOTALS	16	122	
PROJECT TOTALS	56	619	

LIME MODIFIED SOIL

LOCATION STATION TO STATION	PROCESSING MODIFIED SOIL 12"	LIME	REMARKS
	SQ YD	TON	
WILLIAMSON COUNTY			
FAS 2887 (IL 37)			
STA 529+50 TO 537+90	3547	70.3	
STA 551+50 TO 560+90	3969	78.6	
LOCATION TOTAL	7516	148.9	
WILLIAMSON COUNTY PROJECT TOTALS	7516	148.9	
PROJECT TOTAL	7516	148.9	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY