

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	36
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* FAU 9481, FAS 2887 (IL 37)
 ** (12,12X),RS-3;12B-1,12B1-1
 *** FRANKLIN AND WILLIAMSON

BRIDGE CONNECTOR PAVEMENT

LOCATION STATION TO STATION	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	BRIDGE DECK GROOVING	PROTECTIVE COAT (50300300)	PROTECTIVE COAT (42001300)
	SQ YD	SQ YD	SQ YD (BRIDGE)	SQ YD (ROADWAY)
FRANKLIN COUNTY				
FAU 9481 (IL 37)				
STA 90+71 TO 91+29				155
TOTAL FROM ENTRANCE SCHEDULE				0
LOCATION TOTAL	0	0	0	155
FAS 2887 (IL 37)				
STA 372+34 TO 372+40	27	27		27
STA 374+60 TO 374+66	27	27		27
TOTAL FROM SN 028-0078 BILL OF MATERIALS		934	1173	504
TOTAL FROM ENTRANCE SCHEDULE				504
LOCATION TOTAL	54	988	1173	558
FRANKLIN COUNTY PROJECT TOTALS	54	988	1173	713
WILLIAMSON COUNTY				
FAS 2887 (IL 37)				
TOTAL FROM ENTRANCE SCHEDULE				834
LOCATION TOTAL	0	0	0	834
WILLIAMSON COUNTY PROJECT TOTALS	0	0	0	834
PROJECT TOTAL	54	988	1173	1547

CONCRETE HEADWALL REMOVAL

LOCATION STATION TO STATION	CONCRETE HEADWALL REMOVAL	FOR INFO ONLY	REMARKS
	EACH	CU YD	
FRANKLIN COUNTY			
FAU 9481 (IL 37)			
RT STA 80+06	1	0.2	JUST NORTH OF WILLIAMS DRIVE
LOCATION TOTAL	1	0.2	
FAS 2887 (IL 37)			
LT STA 378+61	1	2.6	RET. WALL BLOCKS NEAR K&E TECH
LT STA 379+02	1	2.1	RET. WALL BLOCKS NEAR K&E TECH
STA 426+46	2	0.9	
LOCATION TOTAL	4	5.6	
FRANKLIN COUNTY PROJECT TOTALS	5	5.8	
WILLIAMSON COUNTY			
FAS 2887 (IL 37)			
RT STA 457+48	1	0.1	NORTH END OF CULVERT
RT STA 457+81	1	0.1	SOUTH END OF CULVERT
STA 484+01	1	0.2	
RT STA 498+19	1	0.2	NORTH END OF CULVERT
RT STA 498+99	1	0.3	SOUTH END OF CULVERT
STA 501+87	2	0.5	
STA 510+92	1	0.2	
RT STA 515+79	1	0.1	NORTH END OF CULVERT
RT STA 518+91	1	0.7	NORTH END OF CULVERT
RT STA 519+32	1	0.6	SOUTH END OF CULVERT
STA 525+02	2	3.5	
LT STA 551+58	1	0.5	NORTH END OF CULVERT
LT STA 551+90	1	0.6	SOUTH END OF CULVERT
LT STA 552+37	1	0.1	SOUTH END OF CULVERT
RT STA 552+47	1	0.1	SOUTH END OF CULVERT
LT STA 556+51	1	0.1	NORTH END OF CULVERT
LT STA 570+67	1	0.1	NORTH END OF CULVERT (MOORE'S LANE)
LT STA 571+08	1	0.1	SOUTH END OF CULVERT (MOORE'S LANE)
LT STA 574+07	1	0.1	NORTH END OF CULVERT
LOCATION TOTAL	21	8.2	
WILLIAMSON COUNTY PROJECT TOTALS	21	8.2	
PROJECT TOTAL	26	14.0	

PLOT DATE = 12/7/2009
 FILE NAME = c:\pvc\work\p1001\HEADCON.dwg
 PLOT SCALE = 5/8"=1'-0"
 USER NAME = headcon

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY