CONTRACT NO. 98823

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	41
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

* FAU 9481, FAS 2887 (IL 37)
** (12,12X),RS-3;12B-1,12B1-1
*** FRANKLIN AND WILLIAMSON

EROSION CONTROL

LOCATION STATION TO STATION	PROPOSED DITCH WIDTH FEET	EROSION CONTROL BLANKET SQ YD	HEAVY DUTY EXCELSIOR BLANKET SQ YD	TEMPORARY DITCH CHECKS FOOT	PERIMETER EROSION BARRIER FOOT	INLET & PIPE PROTECTION EACH	REMARKS
RT STA 521+76 TO 524+78	8	268		30			
RT STA 525+28 TO 525+66	8	34					
RT STA 525+88 TO 527+76	8	167		20			
RT STA 527+92 TO 528+60	8	60					
RT STA 528+93 TO 530+03	8	98		10			
RT STA 530+48 TO 531+75	4	56		10			
RT STA 532+40 TO 533+70	8	116		10			
RT STA 534+14 TO 537+90	4	167		20			
RT STA 538+35 TO 543+00	8	413		50			
RT STA 543+00 TO 543+38	8		34	20			
RT STA 543+58 TO 544+00	8		37	10			
RT STA 544+00 TO 544+48	8	43					
RT STA 544+91 TO 547+34	8	216		50			
RT STA 547+61 TO 548+98	8	122		30			
RT STA 549+65						1	INLET
RT STA 550+87 TO 552+15	4	57		10			
RT STA 552+64 TO 553+33	4	31					
RT STA 553+64 TO 554+29	4	29					
RT STA 555+74 TO 559+53	8	1684		50			
RT STA 559+91 TO 561+10	8	423		10			
RT STA 561+10 TO 567+86	8	601		70			
RT STA 568+13 TO 568+47	8		30			1	
RT STA 572+50 TO 573+35	8	76					
RT STA 573+68 TO 575+65	8	175		10			
RT STA 576+53 TO 577+41	8	78					
DETOUR ROAD NO. 1							
LT STA 1+00 TO 2+32 STAGE 1		147		10			
LT STA 3+12 TO 3+75 STAGE 1		70					
LT STA 3+75 TO 4+39 STAGE 1			71	20			
LT STA 4+70 TO 7+85 STAGE 1		350		50			
LT STA 8+05 TO 8+70 STAGE 1		72		10			
LT STA 9+09 TO 10+00 STAGE 1		101		10			
LT STA 10+40 TO 12+12 STAGE 1		191		30			
LT STA 12+12 TO 12+70 STAGE 1		64		10			
LT STA 12+12 STAGE 1						1	
RT STA 4+43 TO 7+67 STAGE 1		360		30			
RT STA 4+43 STAGE 1						1	
RT STA 8+39 TO 10+15 STAGE 1		196		20			
RT STA 10+43 TO 10+83 STAGE 1		44					
RT STA 7+67 TO 8+39 STAGE 2		80					
RT STA 10+15 TO 10+43 STAGE 2		31					
DETOUR ROAD NO. 2							
LT STA 3+82 TO 4+79 STAGE 1		108		10			
LT STA 5+23 TO 5+75 STAGE 1		58		10			
LT STA 6+26 TO 6+75 STAGE 1		54		10			
LT STA 7+37 TO 11+10 STAGE 1		414		50			
LT STA 11+10 TO 11+55 STAGE 1			50				
LT STA 11+10 STAGE 1						1	
RT STA 2+64 TO 3+82 STAGE 1		131		10			
RT STA 4+14 TO 4+92 STAGE 1		87		10			
RT STA 5+17 TO 5+75 STAGE 1		64		10			
RT STA 6+06 TO 6+96 STAGE 1		100		10			
RT STA 7+19 TO 11+10 STAGE 1		434		60			
RT STA 11+40 TO 13+25 STAGE 1		206		30			
LT STA 4+79 TO 5+23 STAGE 2		49					
LT STA 5+75 TO 6+26 STAGE 2		57					
LT STA 6+75 TO 7+37 STAGE 2		69					
LOCATION TOTAL		21995	328	1900	0	14	
WILLIAMSON COUNTY PROJECT TOTALS		21995	328	1900	0	14	
PROJECT TOTAL		33270	774	3100	3135	28	

SHEET 4 OF 4

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ. NO SCALE

DRAWN BY CNH

DATE

CHECKED BY

PLOT DATE = 12/8/2009
FILE NAME = c:\pw_wor-k\PWIDOT\WEEMSBF\dms43590\d98402dbv.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = weemsbf