CONTRACT NO. 98823

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	42
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

* FAU 9481, FAS 2887 (IL 37)
** (12,12X),RS-3;12B-1,12B1-1
*** FRANKLIN AND WILLIAMSON

RAISED PAVEMENT MARKING

LOCATION STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER			REMARKS
	ONE WAY CRYSTAL	TWO WAY AMBER	REMOVAL	
	EACH	EACH	EACH	
FRANKLIN COUNTY				
FAU 9481 (IL 37)				
STA 79+75 TO 94+19.21 BK		18	18	
STA 366+03.65 AH TO 374+30		10	10	
LOCATION TOTAL	0	28	28	
FAS 2887 (IL 37)				
STA 374+30 TO 382+93.50 BK		11	11	
STA 382+98.60 A TO 457+12		93	93	
STA 403+89 TO 406+53	7		7	COUNTRY CLUB TURN LANE
LOCATION TOTAL	7	104	111	
FRANKLIN COUNTY PROJECT TOTALS	7	132	139	
WILLIAMSON COUNTY				
FAS 2887 (IL 37)				
STA 457+12 TO 477+33.40 BK		25	25	
STA 477+39.79 AH TO 577+41		125	125	
LOCATION TOTAL	0	150	150	
WILLIAMSON COUNTY PROJECT TOTALS	0	150	150	
PROJECT SUBTOTAL	7	282		
PROJECT TOTAL	289		289	

TEMPORARY ACCESS

LOCATION STATION TO STATION	AGGREGATE FOR TEMPORARY ACCESS	REMARKS
	TON	
WILLIAMSON COUNTY		
FAS 2887 (IL 37)		
STA 528+66	11	
STA 529+12	12	
STA 529+67 TO 532+07	172	TEMP ACCESS RD/SEE DETOUR RD #1 PLAN
STA 530+74	12	
STA 534+26	11	
STA 536+44	34	VILLA WAY ROAD
STA 539+13	20	
STA 550+17	23	
STA 550+77	14	
STA 551+76	47	UNION ROAD
STA 553+48	10	
STA 554+51	13	
STA 555+51	12	
STA 559+72	11	
STA 561+00	128	TEMP ACCESS RD/SEE DETOUR RD #2 PLAN
STA 11+12	59	TEMP PRIVATE ENTRANCE AT UNION RD
WILLIAMSON COUNTY PROJECT TOTALS	589	
PROJECT TOTAL	589	

RIPRAP

LOCATION STATION TO STATION	STONE RIPRAP CLASS A3	STONE RIRRAP CLASS A4	STONE DUMPED RIPRAP CLASS A4	FILTER FABRIC	REMARKS
	TON	SQ YD	SQ YD	SQ YD	
FRANKLIN COUNTY					
FAS 2887 (IL 37)					
RT STA 389+25		57		57	DITCH LINING
RT STA 399+50	67				DITCH LINING
RT STA 399+98			25		ENERGY DISSIPATOR
RT STA 426+46			33		ENERGY DISSIPATOR
LT STA 436+37	29				DITCH LINING
RT STA 436+37	38				DITCH LINING
RT STA 454+88			17		ENERGY DISSIPATOR
TOTAL FROM SN 028-0078 BILL OF MATERIALS		862		862	
TOTAL FROM SN 028-2017 BILL OF MATERIALS		189		189	
FRANKLIN COUNTY TOTALS	134	1,108	75	1,108	
WILLIAMSON COUNTY					
FAS 2887 (IL 37)					
RT STA 469+98			13		ENERGY DISSIPATOR
LT STA 484+01			17		ENERGY DISSIPATOR
RT STA 501+87			18		ENERGY DISSIPATOR
RT STA 510+92			11		ENERGY DISSIPATOR
RT STA 525+03			206		ENERGY DISSIPATOR
RT STA 543+48			44		ENERGY DISSIPATOR
RT STA 569+00			75		ENERGY DISSIPATOR
WILLIAMSON COUNTY TOTALS	0	0	384	0	
PROJECT TOTALS	134	1108	459	1108	

NOTE: THE AVERAGE DIMENSIONS INDICATED WERE USED TO ESTIMATE PAY QUANTITIES ONLY AND ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES. ACTUAL DIMENSIONS TO BE DETERMINED BY THE ENGINEER.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. NO SCALE HORIZ.
DATE

DRAWN BY CNH
CHECKED BY

PLOT DATE = 12/7/2009
FILE NAME = c:\projects\PWIDOT\HEADCN\dms43658\d1904003sm-dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = headcn