

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	304	44

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT  
 \* FAU 9481, FAS 2887 (IL 37)  
 \*\* (12.12X).RS-3;12B-1,12B1-1  
 \*\*\* FRANKLIN AND WILLIAMSON

### PAVEMENT MARKING

LOCATION STATION TO STATION	*SHORT-TERM PAVEMENT MARKING FOOT	PAVEMENT MARKING TAPE, SPECIAL TYPE III		TEMPORARY PAVEMENT MARKING LINE					PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	PAINT PAVEMENT MARKING				REMARKS	
		WHITE FOOT	YELLOW FOOT	LETTERS AND SYMBOLS SQ FT	LINE 4"			LINE 24"			LETTERS AND SYMBOLS SQ FT	LINE 4"				LINE 24"
					SOLID WHITE FOOT	SKIP-DASH YELLOW FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT				SOLID WHITE FOOT	SOLID WHITE FOOT	SKIP-DASH YELLOW FOOT		SOLID YELLOW FOOT
<b>FRANKLIN COUNTY</b>																
<b>FAU 9481 (IL 37)</b>																
STA 79+75 TO 94+19	432							2888		360	144			2888	360	SINGLE DASH
STA 366+03 TO 371+93	180							1180		150	60			1180	150	SINGLE DASH
STA 371+93 TO 374+30	72							474		60	237			474	60	DASH AND SOLID
<b>STAGE 1 BOX CULVERT CONSTRUCTION</b>																
RT STA 88+05 TO 93+30			525												175	
LT STA 88+19 TO 94+06			587	150											246	
RT STA 88+00 TO 93+50											184					EXISTING EDGELINE
STA 88+00 TO 94+06											20					EXISTING CENTERLINE
<b>STAGE 2 BOX CULVERT CONSTRUCTION</b>																
RT STA 87+69 TO 93+81			612	160											257	
LT STA 88+70 TO 93+50			480												160	
LT STA 88+50 TO 93+50											148					EXISTING EDGELINE
<b>STAGE 1 BRIDGE CONSTRUCTION</b>																
RT STA 371+00 TO 376+00			500												167	
LT STA 370+61 TO 376+86			625	160											262	
RT STA 371+00 TO 376+00											167					EXISTING EDGELINE
STA 370+61 TO 376+86											21					EXISTING CENTERLINE
<b>STAGE 2 BRIDGE CONSTRUCTION</b>																
RT STA 369+11 TO 376+91			780	200											327	
LT STA 370+00 TO 376+50			650												217	
LT STA 370+00 TO 376+50											143					EXISTING EDGELINE
STA 369+11 TO 370+61											13					EXISTING CENTERLINE
LOCATION TOTAL	684	4759	670	0.0		4542	570	237	0	696	2039	0.0	4542	570	237	0
<b>FAS 2887 (IL 37)</b>																
STA 374+30 TO 377+95	108					730	90	365			36		730	90	365	DASH AND SOLID
STA 377+95 TO 380+06	60					422	60				20		422	60		SINGLE DASH
STA 380+06 TO 382+93	84					574	70	287			28		574	70	287	DASH AND SOLID
STA 382+98 TO 385+61	84					526	70	263			28		526	70	263	DASH AND SOLID
STA 385+61 TO 413+22	828					5522	690				276		5522	690		SINGLE DASH
STA 413+22 TO 418+02	144					960	120	480			48		960	120	480	DASH AND SOLID
STA 418+02 TO 419+43	48					282	40				16		282	40		SINGLE DASH
STA 419+43 TO 422+91	108					696	90	348			36		696	90	348	DASH AND SOLID
STA 422+91 TO 427+87	144					992					48		992			DOUBLE SOLID
STA 427+87 TO 434+21	192					1268	160	634			64		1268	160	634	DASH AND SOLID
STA 434+21 TO 435+74	48					306		306			16		306		306	DOUBLE SOLID
STA 435+74 TO 439+22	108					696	90	348			36		696	90	348	DASH AND SOLID
STA 439+22 TO 442+34	96					624	80				32		624	80		SINGLE DASH
STA 442+34 TO 447+62	156					1056	130	528			52		1056	130	528	DASH AND SOLID
STA 447+62 TO 457+12	288					1900	240				96		1900	240		SINGLE DASH
STA 404+00 TO 406+68	84					268					28		268			TURN LANE
STA 405+40												20.8				"ONLY" SYMBOL
STA 405+90												15.6				RIGHT TURN ARROW
STA 9+05 COUNTRY CLUB ROAD															20	STOP BAR
LOCATION TOTAL	2580	0	0	36.4		16822	1930	4551	20	0	860	36.4	16822	1930	4551	20
<b>FRANKLIN COUNTY PROJECT TOTALS</b>	<b>3264</b>	<b>4759</b>	<b>670</b>	<b>36.4</b>		<b>21364</b>	<b>2500</b>	<b>4788</b>	<b>20</b>	<b>696</b>	<b>2899</b>	<b>36.4</b>	<b>21364</b>	<b>2500</b>	<b>4788</b>	<b>20</b>

\*DENOTES THREE APPLICATIONS

SHEET 1 OF 2

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>SCHEDULE</b>

SCALE: VERT. NO SCALE  
 HORIZ. DATE  
 DRAWN BY CNH  
 CHECKED BY