



SEEDING CLASS 2, SPECIAL AND EROSION CONTROL BLANKET

- ① 13'-3" EXISTING TRAFFIC BARRIER TERMINAL, TYPE 5A - TO REMAIN IN PLACE
- ② 36'-9" REMOVE & RE-ERECT STEEL PLATE BEAM GUARDRAIL
- ③ 37'-6" STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS
- ④ 62'-6" STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS
- ⑤ 50'-0" TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

NOTES: SEE GUARD RAIL TABLE FOR STATIONING AND QUANTITY  
 EXISTING T.B.T. TYPE 1 (BLR 23-3) TO BE REMOVED = (3 EACH @ 25FT LENGTH)  
 630301-05 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS SHALL BE COMPLETED BY OTHERS UNDER SEPARATE CONTRACT.

FILE NAME = 078315-shr-plan28.dgn	USER NAME =	DESIGNED - A.S.L.	REVISED -
		DRAWN - D.T.M.	REVISED -
	PLOT SCALE =	CHECKED - S.W.M.	REVISED -
	PLOT DATE = 2/5/2010	DATE - 11/18/09	REVISED -

**STATE OF ILLINOIS**  
**JACKSON COUNTY HIGHWAY DEPARTMENT**



**GUARDRAIL DETAILS AND SEEDING PLAN**  
**C.H. 30 / F.A.S. 1919 / BOSKEYDELL ROAD**

F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1919	06-00057-02-BR	JACKSON	6	4
CONTRACT NO. 99414				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT BRS-1919 (107)				

SCALE: 1" = 20' SHEET NO. 1 OF 1 SHEETS STA. 10+50 TO STA. 16+80